

Department of Public Works

 W240 N3065 Pewaukee Road

 Pewaukee, WI 53072

 DPW Main Office:
 691-0804

 Yater and Sewer Division:
 691-0804

 Street Division:
 691-0771

 Fax: 691-5729

 Street Division:
 691-0771

 Fax: 691-5729

 Engineering Division:
 691-0804

PUBLIC WORKS COMMITTEE MEETING NOTICE AND AGENDA Thursday, April 22, 2021 6:00 PM

Common Council Chambers W240N3065 Pewaukee Road ~ Pewaukee, Wisconsin

Call to Order and Pledge of Allegiance

- 1. Public Comment Please limit your comments to 2 minutes. If further time for discussion is needed, please contact your local Alderperson prior to the meeting.
- 2. <u>Communications</u>
- 3. Discussion and Action Regarding the Minutes
- 4. Old Business
- 5. <u>Storm Water Management Division</u>
 - 5.1. Discussion and possible action regarding the 2020 Annual Report for the MS4 Permit.
 - 5.2. Discussion and possible action regarding Kathryn Court/Springdale Estates Flood Mitigation Project alternatives.
- 6. <u>Water and Sewer Division</u>
 - 6.1. Discussion and possible action regarding the Well 5 HMO Treatment Facility & Building update.
- 7. Status Reports
- 8. Engineering Division
 - 8.1. Discussion and possible action regarding a pedestrian crossing across Green Road from Littlefield Court to private Five Fields Park.
 - 8.2. Discussion and possible action to establish future meeting date and times.
 - 8.3. Discussion and possible action regarding Duplainville Road Reconstruction and Trail construction including Lindsay Road Trail construction.
 - 8.4. Discussion regarding Novus Training for Committee Members.
- 9. <u>Highway Division</u>
- 10. Public Comment Please limit your comments to 2 minutes. If further time for discussion is needed, please contact your local Alderperson prior to the meeting.

11. Adjournment

Jeff Weigel Director of Public Works

April 20, 2021

NOTICE

It is possible that members of other governmental bodies of the municipality may be in attendance to gather information that may form a quorum. At the above stated meeting, no action will be taken by any governmental body other than the governmental body specifically referred to above in this notice.

Any person who has a qualifying disability under the Americans with Disabilities Act that requires the meeting or materials at the meeting to be in an accessible format must contact the DPW Main Office, at (262) 691-0804 by 12:00 p.m. the Tuesday prior to the meeting so that arrangements may be made to accommodate your request.

CITY OF PEWAUKEE PUBLIC WORKS COMMITTEE AGENDA ITEM 5.1.

DATE: April 22, 2021

DEPARTMENT: PW - Stormwater

PROVIDED BY:

SUBJECT:

Discussion and possible action regarding the 2020 Annual Report for the MS4 Permit.

BACKGROUND:

FINANCIAL IMPACT:

RECOMMENDED MOTION:

ATTACHMENTS: Description

2020 Annual MS4 Report Memo 2020 Annual MS4 Report



Department of Public Works Engineering Division W240N3065 Pewaukee Road Pewaukee, WI 53072 (262) 691-0804 Fax: (262) 691-5720

Memorandum

To:Magdelene Wagner, P.E.From:Richard J. Wirtz, P.E., CFMSubject:City of Pewaukee Annual MS4 Report for 2020

Date: March 31, 2021

The Wisconsin Department of Natural Resources changed the format of the annual report to an electronic filing process as of 2017. The eReporting system provides the DNR a standardized method and form for receiving reports from permitted communities whom must report on specific program components and the measureable goals of their permit. However, this standardized method of reporting may not provide enough information to interested residents or elected officials of the City who are unfamiliar with the programs and processes required by the City's MS4 permit. As in the previous three reporting cycles, we are providing a brief summary report to be posted on the City's website and provided to members of the Common Council which briefly describes the major components of the City's permit, the measurable goals of these components, the results achieved during the reporting year and any recommended changes to the programs. This summary report as well as the information provided in Items B, C, D and E were submitted to the DNR along with the City's eReport. A copy of the 2020 eReport filed with the DNR is attached at the end of the report as Item A.

P:\City\NR 216 Permit\Annual Reports\2020_due 3-31-2021\Annual Report\Mar 31, 2021_memo_presentation of MS4 annual report to dnr.docx

CITY OF PEWAUKEE ANNUAL REPORT TO THE DEPARTMENT OF NATURAL RESOURCES IN ACCORDANCE WITH NR216 PERMIT REQUIREMENTS

SUBMITTED MARCH 31, 2021

Illicit Discharge Detection and Elimination/Spills Response Program

Description of Program

The purpose of the Illicit Discharge Detection and Elimination program as well as the Spills Response program is to prevent harmful substances from entering the City's Municipal Separate Storm Sewer System (MS4) and being discharged to waters of the state. The Illicit Discharge Detection and Elimination program incorporates field screening procedures of 20 major outfalls for the purpose of detecting, investigating and eliminating discharges to the MS4 system which are not entirely composed of storm water. The Spills Response program is a procedure for responding to, investigating and remediating material spills which could enter the City's MS4 system.

Measurable Goals

Perform field screening of the City's major outfalls to determine if illicit discharges are occurring and document the findings. The measurable goal of the Spills Response program is to document and report on the spills reported to the City.

Results Achieved

City staff performed biannual field screening of the 20 major outfalls identified in its plan. There were no illicit discharges detected during the field screening program.

The City of Pewaukee Fire Department (PFD) responded to a diesel fuel leak on August 31, 2020. Approximately 50 gallons of fuel had spread over a 150 square foot area of pavement on Spring Hill Drive. The fuel did not enter into the City's MS4 system or enter any waterways. Ten 5 gallon bags of oil dry was used to mitigate the spill along with additional oil dry provided by the contractor. The Department of Natural Resources (DNR) and the City Department of Public Works were both contacted. The contractor was responsible for cleanup of the oil absorbent products applied to the roadway which was verified by the PFD later that day. Follow up conversations were conducted with the DNR and additional evaluations were made by the PFD to evaluate staining of the roadway and any remaining odor.

City Staff responded to a potential illicit discharge to the road side ditch system along Lexington Drive. A resident was complaining of a sewage odor coming from the water in the ditch line. The complaint was initially investigated by the City's Water and Sewer Utility Staff before forwarding to Engineering Staff. The discharge originated in the City of Waukesha and was being investigated by their Staff. At the time City of Pewaukee Engineering Staff conducted their field evaluation, there was no odor present within the ditch lines and all remaining water was clear. The City of Pewaukee was later informed by the City of Waukesha that the discharge was pool water from a multi-family development in the City of Waukesha.

Describe Any Planned Changes to the Program

City staff have been unable to complete a re-evaluation of the outfalls selected for field screening in 2020. The City's MS4 map needs to be adjusted based upon inventory data collected on the City's storm sewer system between 2014 and 2016. Staff anticipate updating the City's MS4 map and re-evaluating the program in conjunction with the preparation of a comprehensive storm water management plan to be conducted in 2021/2022. Any program re-evaluation will be consistent with the recommendations provided in DNR program guidance document 3800-2012-01.

Construction Site Pollutant Control

Description of Program

The City regulates land disturbing activity according to Chapters 14 and 19 of the Municipal code. Chapter 14 of the Municipal Code pertains to the design, construction, alteration, demolition and moving of buildings and structures within the City and associated land disturbing construction activities. The requirements of this chapter are regulated and enforced by the City's Building Inspection Department. Chapter 19 of the Municipal Code pertains to construction site erosion control, post construction site storm water management and illicit discharges. Regulation and enforcement of the requirements of this chapter are conducted by the City's Engineering Department. The construction site erosion control requirements of the ordinance are consistent with the provisions of NR 216 and the performance standards of NR 151 of the Administrative Code.

Measurable Goals

The Engineering Department reviews proposed development for conformance with the erosion control requirements of Chapter 19 of the Municipal Code and issues a Certificate of Permit Coverage for development plans meeting the requirements of the ordinance. The Department and its consultants also conduct weekly and post 0.5-inch rainfall event compliance inspections of permitted construction sites for the purpose of maintaining compliance with Chapter 19 of the Municipal Code. A report is generated for each inspection performed and provided to the owner/designated representatives of the permitted site. The inspection reports detail any maintenance to be performed, deficiencies noted and/or additional BMP's required to maintain compliance. Sites which are out of compliance are subject to enforcement which can include issuing Notices of Noncompliance, Notices of Violations, issuing fines, posting stop work orders and revoking permits.

The Building Inspection Department issues erosion control permits for land disturbing construction activities associated with buildings and structures. Inspections of the erosion control best management practices are performed on sites with disturbances less than 1 acre in area. Inspections are performed each time the Building Inspector is on a site having an erosion control permit.

Results achieved

The Engineering Department issued 4 erosion control permits for new development and conducted approximately 389 compliance inspections in 2020. Eight Notices of Noncompliance, four Notices of Violation, one Enforcement Conference and \$8500.00 in Recommendations for Fines were issued during the reporting year.

The Building Inspection Department conducted approximately 209 erosion bond and 108 erosion control inspections in 2020.

Describe Any Planned Changes to the Program

None at this time.

Post-Construction Site Storm Water Management

Description of Program

The City regulates post-construction site storm water management according to Chapter 19 of the Municipal code. The post-construction storm water management requirements are compliant with the applicable provisions of NR 216 and the performance standards contained in NR 151 of the Administrative Code regarding infiltration and TSS reductions. However, the City's ordinance is more restrictive than the performance standards contained in NR 151 in terms of the pre- and post-developed discharge rates from the site. The City's ordinance generally requires the discharge from the 1, 2, 10 and 100-year storm events from the post developed site be at or below the discharge rates from the site under pre-settlement conditions. Post construction site storm water management practices are required to be maintained and the City requires a maintenance agreement be executed and recorded at Waukesha County Register of Deeds for the perpetual maintenance of the practices.

Measurable Goals

The City reviews proposed development plans for conformance with the post-construction site storm water management requirements of Chapter 19 of the Municipal Code and issues a Certificate of Permit Coverage for development plans meeting the requirements of the ordinance.

Results Achieved

The City issued 2 permits for post-construction site discharges from new development in 2020. City Staff and consultants have conducted reviews of submittals for 6 different proposed developments for compliance with the post-construction site storm water management requirements of the Municipal Code during the reporting year.

Describe Any Planned Changes to the Program

The City is in the process of documenting its storm water management program and formalizing procedures for inspection and tracking of existing storm water management facilities built to comply with Chapter 19 of the Municipal Code and NR 216 and NR 151 of the State Statutes. This work has generally been delayed by the review, permitting and enforcement of the City's construction site erosion control and post-construction site storm water management ordinance. To date the bulk of the program has been documented and forms have been created for the inspection of various storm water management practices. Remaining work items include: drafting the procedures for the inspections, maintenance and violations of the post-construction site BMP's. City Staff continue to locate and compile available data on the existing storm water management facilities that have been constructed over the years. This data will aid in the inspection of these facilities and determine what agreements are in place for the maintenance of these facilities. A copy of the draft program is included as Item B along with copies of the inspection forms created thus far.

Pollution Prevention

The City is required to implement a number of programs under the Pollution Prevention criteria identified within its WPDES permit. These programs are:

- 1. Inspection, maintenance and inventory of post-construction site storm water management facilities.
- 2. Catch basin cleaning program.
- 3. Street sweeping program.
- 4. Winter road management program.
- 5. Leaf management program.
- 6. SWPPP for municipal facilities.
- 7. Nutrient management plan for municipal properties with pervious surfaces over 5 acres.
- 8. Management procedures for unplanned water main discharges.
- 9. Other Reportable Results.

The following will provide a brief summary of each of the above programs, identify the measurable goals (if any), the results achieved and any planned program changes or improvements.

Inspection, Maintenance and Inventory of Post-Construction Site Storm Water Management Facilities

Description of Program

The program consists of an inventory of the existing storm water management facilities and ensuring the facilities are properly maintained to perform according to the performance standards used for the design of the facility. The City owns 8 municipal facilities between Wagner Park, the City Hall Campus and the newly constructed Pewaukee Sports Complex.

Measurable Goals

In 2010 the City identified through aerial photographs approximately 192 facilities within the municipal boundaries that were potential storm water BMP's implemented to control post-developed discharges and/or provide for TSS reduction. A significant amount of information still needs to be collected from available City records in order to complete the inventory and adequately conduct inspections of the facilities.

The inventory includes such items as the location, general condition, age and ownership of each facility; whether a long term maintenance agreement exists for the facility; the general design of the facility; results of any previous inspections; and completion of any previously recommended maintenance and repairs.

The two municipal facilities located in Wagner Park are inspected annually by City Staff. Five of the remaining six facilities (4 facilities at the Pewaukee Sports Complex, 1 bioretention facility at Wagner Park and 1 bioretention facility at the City Hall Campus site) were inspected in 2020, the exception being the bioretention facility at Wagner Park. Asbuilt surveys of the Sports Complex ponds, the City Hall biofiltration device and the Wagner Park biofiltration device were not completed during the reporting year.

Results achieved

As indicated previously, City Staff have begun and continue to locate and compile available data on the existing storm water management facilities that have been constructed over the years. To date, approximately 28 pond asbuilts, 30 maintenance agreements and 92 storm water management plans have been located and scanned into the City's network.

Inspections of the 2 wet ponds at Wagner Park, 1 wet pond at the Pewaukee Sports Complex and the City Hall biofiltration device show the facilities are in need of maintenance activities. City Staff also conducted 2 inspections of privately owned storm water management ponds and received an additional 6 inspection reports from private facility owners.

Describe Any Planned Changes to the Program

The completion of the inventory is still lagging due to the time requirements of other permit programs. As time allows staff will work on the completion of the inventory, preparation of inspection forms and the development of procedures for conducting and tracking inspections. This work element shares many of the components which are in process of being prepared as a part of the Post Construction Site Storm Water Management Program.

Catch Basin Cleaning Program

Description of Program

The City identified 12 catch basins along Peterson Drive in 2005 to be inspected and cleaned annually when the program proposal was initially created. This list has been expanded to include 69 catch basins along Green Road which were installed as a part of a road construction project in 2013. This program has also been expanded to include the maintenance and repair of the City's existing storm sewer structures

Measurable Goals

To ensure the continued function of the MS4 system and to remove sediment deposits from the system.

Results achieved

Approximately 26 tons of solids were removed as a result of catch basin cleanings in 2020. Additionally, 13 storm sewer structures were repaired by the Highway Department in 2020. The City released a contract in late 2020 for the repair or replacement of approximately 228 storm sewer structures. As of the end of 2020, approximately 48 storm sewer structures had been repaired or replaced.

Describe Any Planned Changes to the Program

The program needs to be updated to include the catch basins installed along Green Road and to include the maintenance and repairs of the storm inlets and manholes that has been occurring annually over the last several years. Previously storm sewer structures were repaired in conjunction with road reconstruction and road maintenance projects as a part of the City's road program. Due to the number of structures requiring immediate attention, maintenance efforts have been accelerated. From 2015 to 2019 over 446 storm sewer structures have been repaired or replaced.

Street Sweeping Program

Description of Program

The City Highway Department is responsible for the sweeping of the City Streets. The current program consists of sweeping all City streets once in the spring (as soon as the snow melts) and sweeping once in the fall all City streets with a curb and gutter cross-section. Additionally, City crews sweep arterial streets once per week for 1.5 months in the spring (as soon as the snow cover permits).

Measurable Goals

To remove sediment and debris from the road surface and gutter line prior to being transported by runoff into the City's MS4 system.

Results Achieved

Approximately 96 hours were spent sweeping 804 miles of streets in 2020. This effort removed approximately 68.2 tons of solids prior to entering into the City's MS4 system.

Describe Any Planned Changes to the Program

None at this time.

Winter Road Management Program

Description of Program

The winter road management program prescribes the methodologies and guidelines for the removal and control of snow and ice buildup on the City's streets. The City Highway Department is responsible for establishing the procedures, methods, equipment and labor to implement the program. Details of the program evolve coincident with the evolution of technology and experience within the department regarding snow and ice removal.

Measurable Goals

The goal of the program is to maintain the roadway in a safe driving condition within the limitations of resources, climactic conditions, preservation of the driving surface and environmental concerns. In balancing these concerns, the department is recommended to strive for "passable roadway" conditions on the driving lanes during the storm event. A "passable roadway" is defined as a roadway surface that is free from drifts, snow ridges and as much ice and snowpack as is practical and can be traveled safely at reasonable speeds.

Secondary to maintaining safe driving conditions is the reduction of the amount of salts used during a winter storm event. To this extent the City has invested in equipment which allows for the use of a salt brine for pre-wetting of salt or as a stand-alone pre-treatment of the pavement surface. As a stand-alone treatment, salt brine helps to prevent ice/snow from bonding to the pavement surface thereby providing for easier removal during plowing operations. When used to pre-wet dry salt prior to application to a pavement surface, the brine helps to maintain the salt on the pavement surface rather than be displaced into the ditch or curb line. In either case the salt brine is anticipated to reduce the amount of dry salt required to achieve a "passable roadway."

The equipment utilized by the Highway Department is calibrated annually. Salt applications are set based upon the ground speed of the vehicle and the temperature of the pavement. The brine solution used for prewetting the salt is set not to exceed 10 gallons per ton with 8 gallons per ton being typical.

City Staff from the Highway Department attend training periodically regarding winter management operations. The last training event was held in 2016 (Smart Salting Level 1) with seven members of the Highway Department attending. One City Staff member from the Engineering Department attended the Wisconsin Salt Wise training over the winter in 2021 and received certification as an applicator.

Results Achieved

The Highway Department maintains records of each event during the winter season which includes the amount of product used, pertinent weather data, hours worked, number of trucks in service and other measurable data. These records are maintained for the purpose of evaluating the program on a yearly basis. Snowfall totals used in this evaluation are taken from the weather station at Milwaukee International Airport.

The amount of salt used for a given event or season is highly variable and dependent on a number of conditions such as but not limited to: air temperature, pavement temperature, type of precipitation, intensity of storm, the miles of road to be maintained and the number of events in a given year. It is therefore difficult to evaluate whether or not the City's salt application is reduced through the use of salt brines for pre-wetting or as a stand-alone pre-treatment from year to year. Table 1 below summarizes the City's salt use for the winter seasons beginning with the 2010-2011 winter season. A typical salt brine solution is composed of 23.3 % salt which yields approximately 2.5 pounds of salt per gallon of brine.

The City implemented the use of salt brines with the 2011-2012 winter season. Prior to that combinations of salt and salt/sand were used in conjunction with plowing for removal of ice and snow from the municipal streets. As can be seen in Table 1, overall salt use in terms of tons/lane mile of roadway has generally been less since initiating the use of salt brines. However, this simplistic evaluation is a little misleading as it does not consider the severity of the winter season or the effort required by road crews to maintain a "passable roadway".

Winter Season	Tons of Salt	Gallons of Salt Brine	Total Tons of Salt	Lane Miles of Roads	Tons of Salt/lane mile
2010-2011	3203*	Dime	3203*	176.4	18.2
2011-2012	1540	14200	1558	176.6	8.8
2012-2013	3520	22679	3548	177.0	20.0
2013-2014	3160	11490	3174	176.8	18.0
2014-2015	2390	4800	2396	179.4	13.4
2015-2016	1865	5100	1871	183.0	10.2
2016-2017	2900	11225	2914	183.0	15.9
2017-2018	3365	5650	3372	184.3	18.3
2018-2019	3365	9070	3376	184.3	18.3
2019-2020	2450	7750	2460	184.3	13.4
2020-2021	2240	7819	2250	185.2	12.2

Table 1. City of Pewaukee Salt Use for Winter Road Management.

*Total includes salt and salt/sand mixture.

The Wisconsin DOT has created a Winter Severity Index (WSI) which it utilizes in evaluating the severity of the winter season in relation to its winter management program. The index considers factors such as number of snow events, amount of snow, number of freezing rain events, storm durations, and number of incidents (frost runs, drifting and clean up). The State DOT developed the WSI in 1995. Prior to the 2013-2014 winter season, index values ranged from 0 to 100. Therefore, the higher the index value, the more severe the winter season and the lower the index value the milder the winter season. The State DOT revised the WSI in the 2013-2014 winter season to provide results which are scaled and compared to the average of the 5 previous winters; the value of which is set as 100. Therefore, values in excess of 100 indicate a severer than average winter and values less than 100 indicate a milder than average winter.

The statewide average WSI is shown in Table 2 for each winter season. Included in Table 2 are values for the WSI for Waukesha County as well. Previously, values for the Waukesha County WSI from 2010 to 2013 were only given in the previous index (weighted from 0 to 100) with the remainder provided in the revised index. The values shown for Waukesha County in Table 2 for those years before the revised index were extrapolated based upon the statewide average values which were available in both versions of the index.

The approximate total snowfall per season and the number of measurable snow events are taken from the Mitchell International weather station in Milwaukee. The average snowfall is based upon the total snowfall for the season divided by the number of measurable events shown.

Figure 1 compares the Winter Severity Index for the statewide average and Waukesha County versus the salt usage for the City of Pewaukee and Waukesha County in tons of salt per lane mile. Overall, the WSI generally coincides with the amount of salt utilized per lane mile to maintain the City's streets in a passable condition for a winter season. The WSI for the 2020-2021 winter season will not be available until the State publishes its Annual Winter Maintenance Report, usually at the end of the year.

As of the writing of this report, the salt use for the 2020-2021 winter season is calculated to be 210 tons lower than the previous season with approximately 2250 total tons of salt used. This translates to approximately 12.2 tons per lane mile of salt applied to City Streets which is 1.2 tons per lane mile lower than the previous year. By comparison, Waukesha County was reported to have utilized approximately 13.7 tons of salt/lane mile for the 2019-2020 winter season which was 0.3 tons per lane mile higher than the City of Pewaukee's application over the same period. The average application for the City of Pewaukee since beginning the use of salt brines in the 2011-2012 winter season to 2020-2021 winter season is approximately 14.9 tons per lane mile. The winter management summary tables for each year of the program are attached to this report as Item C.


Describe Any Planned Changes to the Program

None at this time.

Winter Season	2010 - 2011	2011- 2012	2012- 2013	2013- 2014	2014- 2015	2015- 2016	2016- 2017	2017 - 2018	2018- 2019	2019- 2020	2020- 2021
Approx. Total Snowfall (inches)	61.9	29.6	45.0	63.4	43.0	39.1	37.6	46.7	55.8	36.7	47.0
Number of Measurable Events	45	26	31	52	38	25	23	36	40	31	28
Average Snowfall per event (inches)	1.4	1.1	1.5	1.2	1.1	1.6	1.6	1.3	1.4	1.2	1.7
Total Tons of Salt	3203*	1558	3548	3174	2396	1881	2914	3372	3376	2460	2250
Total Hours Worked	NA	596	1272	1863	903	812	1171	1215	1564	1213	1230
Tons of Salt per lane mile of Road	18.2	8.8	20.0	18.0	13.4	10.2	15.9	18.3	18.3	13.4	12.2
Average Pavement Temp. (degrees F)	NA	NA	NA	20.1	20.9	26.7	25.3	23.1	26.4	28.3	16.8
WisDOT Statewide WSI	119.2	75.4	115.1	133.6	99.3	90.4	91.1	102.9	105.7	94.3	**
WSI for Waukesha County	83.7 ^a	46.3 ^a	79.4 ^a	107.9	64.6	53.2	54.7	81.5 ^b	81.5 ^b	79.1	**
Waukesha County Tons of Salt per Lane mile	22.0	13.2	14.3	22.6	13.7	12.5	19.2	19.8	20.2	13.7	**

Table 2. Comparison of Winter Seasons and City of Pewaukee Salt Use.

*Total includes salt and salt/sand mixture. **Not determined at the time of reporting. ^aExtrapolated values to statewide index. ^bCorrected WSI from previous report.



Page 13 of 93

Leaf Management Program

Description of Program

The City accepts leaves and grass clippings at the City Recycling Center drop off site located on the lower level of the Pewaukee City Hall campus. Material collected at the site is taken to a facility in Menomonee Falls for composting. The City's waste hauler will also pickup leaves and grass clippings for a fee.

Measurable Goals

To provide an alternative means of disposing of leaves and grass clippings for the City residents as opposed to burning or dumping the debris into the City's right-of-way or ditches.

Results Achieved

In previous years yard waste was broken down into categories to determine the mass of leaves taken to the yard waste site. Similar to last year's reporting by Waukesha County the mass of leaves collected is included in the total yard waste collected which was 931 tons of material. The City's waste hauler reported collecting approximately 6.3 tons of yard waste in 2020.

Describe Any Planned Changes to the Program

None at this time.

SWPPP for Municipal Facilities

Description of Program

The City had prepared an update to its Evaluation of Public Works Yard in 2011. The goal of the evaluation was to identify potential sources of non-point pollution and provide recommendations to mitigate these sources. The City provided additional information in the 2015 annual report regarding planned projects to occur within the City "campus" site which would impact operations on site as well as potentially how storm water is handled. These planned projects included the construction of a new water tower, the construction of a new salt storage facility and repairs to the City Hall and highway garage. To date the new water tower and the repairs to City Hall and highway garage have been completed.

Measurable Goals

The goal of the program is to reduce non-point pollutant loadings from the City "campus" site.

Results achieved

An inspection of the Public Works Yard was performed in 2020.

Describe Any Planned Changes to the Program

A facility plan of the Public Works Highway Department was prepared for the City in 2020 to evaluate options for upgrading the existing facility and improvements to operations. To date, it is anticipated to construct a new highway garage at an offsite location. The offsite location would also include provisions for recycling operations, salt brine and salt storage, cold storage and a refueling station. The relocation of the facility and repurposing of the current City Hall Campus site will necessitate the preparation of a new SWPPP.

Nutrient Management Plan for Municipal Properties with Pervious Surfaces over 5 acres

Description of Program

The City has 5 parks with pervious areas over 5 acres: Balmer Park, Wagner Park, South Park, Nettesheim Park and the Pewaukee Sports Complex. A formal nutrient management plan was prepared for the Pewaukee Sports Complex while it was under construction. The remaining parks do not have a formal plan as of yet.

The current practice for maintaining the turf areas in the City's park system is to contract with a company specializing in turf maintenance to assess the condition of the fields and to apply treatments as recommended. Treatments are typically composed of one or more of the following products: Dimension 2EW (a post emergence herbicide); a Urea Nitrogen-Potash fertilizer 25-0-5; a Urea Nitrogen-Potash fertilizer 17-0-5; Trupower 3 (a selective post emergence herbicide); and Cool Power (a selective post emergence herbicide). In addition, the infields of existing baseball fields receive a non-phosphorous fertilizer treatment (composed of a 33-0-5 NPK ratio) three times a year. Mowing of the established turf areas occurs on a weekly rotation with mowing of the baseball infields occurring up to three times a week if necessary.

Measurable Goals

The goal of the program is to reduce the amount of nutrients (namely phosphorous) applied to the turf areas and to apply only what is required to maintain a vigorous growth of vegetation.

Results Achieved

The City's current practices and ordinance bans the use of fertilizers containing phosphorous except for the establishment of new turf areas or if soil tests confirm phosphorous is required.

Describe Any Planned Changes to the Program

Formal plans for the remaining 4 parks need to be developed.

Management Procedures for Unplanned Water Main Discharges

Description of Program

The City is required by permit to develop a program to mitigate discharges of sediment to its MS4 system from unplanned water main discharges otherwise known as "water main breaks." The program was developed for Water and Sewer Utility staff who may be responding to such incidents. The priority for staff responding to a water main break is to locate the source of the discharge and to isolate it, or in layman's terms to "shut it off" as quickly as possible. Temporary erosion control measures, if required, can then be employed to prevent sediment from entering the MS4 system or Waters of the State. The program identifies potential erosion control measures that can be employed to contain/limit the discharge of sediment from a water main break.

Measurable Goals

The goal of the program is to reduce the amount of sediment entering the City's MS4 system or a Water of the State from an unplanned water main discharge.

Results Achieved

The City had 4 unplanned water main discharges last year resulting in an estimated, combined discharge of approximately 575,000 gallons of municipal water.

Describe Any Planned Changes to the Program

None at this time.

Other Reportable Results

Roadways within the City are comprised of a combination of rural cross sections and urban cross sections. Rural cross sections include roadside ditches to collect storm water runoff along with gravel shoulders and paved travel lanes. Urban cross sections include storm sewers and curb and gutter to collect storm water runoff and paved travel lanes. The City of Pewaukee contains approximately 92.6 lineal miles of roads with almost 45 miles of roads having a rural cross-section. Roadside swales need to be periodically cleaned of accumulated sediment to function properly. Each year the City's Highway Department cleans a number of its roadside swales of sediment. Last year the Highway Department cleaned approximately 3632 feet of roadside swales which netted roughly 729 tons of soil.

Worksheets for the Fiscal Analysis required as a part of the City's annual report are included in Item D.

Members of the City's Engineering Staff attended multiple erosion control and storm water management workshops during 2020. These included:

- 2020 Waukesha County Storm Water Management Workshop, May 5-7, 2020 (2 attendees)
- NASECA Construction Site Erosion Control and Storm Water Permit Compliance Training, Dec. 10-11, 2020 (1 attendee)
- Ruekert-Mielke, Inc. webinar, Erosion and Sediment Control Best Management Practices, Apr. 22, 2020 (1 attendee)
- Ruekert-Mielke, Inc. webinar, The MS4 Da Vinci Code, May 20, 2020 (2 attendees)
- NASECA-WI's 17th Annual Conference and Trade Show, Feb. 5-6, 2020 (1 attendee)

Public Education and Outreach and Public Involvement and Participation Programs

Description of Program

The City of Pewaukee along with other members of the Upper Fox River Watershed Group contract with Waukesha County to implement the public education and outreach and public involvement and participation programs as required by Group WPDES permit. The County organizes the plan based upon a target audience. For each target audience a set of activities and goals are defined.

Item E contains the County's 2020 Activity Summary Report identifying the key components of last year's plan, the measurable goals and the results achieved. Also included is the County's 2020-2024 MS4 Public Education and Outreach Plan.

City Staff work with our elected and Municipal officials regarding the City's municipal storm water discharge permit through discussions regarding: the function and need of the City's Storm Water Utility; budget hearings and discussions; discussion regarding potential changes to the City's MS4 permit; changes to the City's post construction site storm water management and construction site erosion control ordinance; discussions related to capital improvement projects that impact storm water discharges; and discussions regarding enforcement of the City's post construction site storm water management and construction site erosion control ordinance.

City Staff knowledgeable of the MS4 permit requirements disseminate this knowledge internally as well as to the public through answering general questions regarding the operations and maintenance of storm water BMP's; questions regarding what storm water utility fees are used for; answering drainage concerns; and discussions regarding how permit requirements impact internal job functions and the burden of reporting requirements.

City Engineering Staff have ongoing discussions educating contractors, developers and engineers regarding: the requirements of the City's construction site erosion control and post construction site storm water management ordinance; the City's Technical Standards; WDNR guidance documents, permit conditions and Technical Standards; and enforcement of erosion control.

Item A

WDNR eReporting System Annual Report

Submittal of Annual Reports and Other Compliance Documents for Municipal Separate Storm Sewer System (MS4) Permits

NOTE: Missing or incomplete fields are highlighted at the bottom of each page. You may save, close and return to your draft permit as often as necessary to complete your application. After 120 days your draft is **deleted**.

Reporting Information

Project Name:	2020 City of Pewaukee Annual Report
County:	Waukesha
Municipality:	Pewaukee, City
Permit Number:	S050105
Facility Number:	30726
Reporting Year:	<u>2020</u>

Required Attachments and Supplemental Information

Please complete the contents of each tab to submit your MS4 permit compliance document. The information included in this checklist is necessary for a complete submittal. A complete and detailed submittal will help us review about your MS4 permit document. To help us make a decision in the shortest amount of time possible, the following information must be submitted:

Annual Report

- Review related web site and instructions for Municipal storm water permit eReporting [Exit Form]
- Complete all required fields on the annual report form and upload required attachments
- Attach the following other supporting documents as appropriate using the attachments tab above
 - Public Education and Outreach Annual Report Summary
 - Public Involvement and Participation Annual Report Summary
 - Illicit Discharge Detection and Elimination Annual Report Summary
 - Construction Site Pollution Control Annual Report Summary
 - Post-Construction Storm Water Management Annual Report Summary
 - Pollution Prevention Annual Report Summary
 - Leaf and Yard Waste Management
 - Municipal Facility (BMP) Inspection Report
 - Municipal Property SWPPP
 - Municipally Property Inspection Report
 - Winter Road Maintenance
 - Storm Sewer Map Annual Report Attachment
 - Storm Water Quality Management Annual Report Attachment
 - TMDL Attachment
 - Storm Water Consortium/Group Report



- Municipal Cooperation Attachment
- Other Annual Report Attachment
- Attach the following permit compliance documents as appropriate using the attachments tab above
 - Storm Water Management Program (S050075-03 General Permit and S058416-04 Madison Area Group Permit shall have a written storm water management program that describes in detail how the permittee intends to comply with the permit requirements for each minimum control measure. Updated programs are due to the department by March 31, 2021.)
 - Public Education and Outreach Program
 - Public Involvement and Participation Program
 - Illicit Discharge Detection and Elimination Program
 - Construction Site Pollutant Control Program
 - Post-Construction Storm Water Management Program
 - Pollution Prevention Program
 - Municipal Storm Water Management Facility (BMP) Inventory (S050075-03 General Permit and S058416-04 Madison Area Group Permit 2.6.1 inventory due to the department by March 31, 2021.)
 - Municipal Storm Water Management Facility (BMP) Inspection and Maintenance Plan (*S050075-03 General Permit and S058416-04 Madison Area Group Permit 2.6.2 document due to the department by March 31, 2021.*)
 - Total Maximum Daily Load documents (*If applicable, see permit for due dates.)
 - TMDL Mapping*
 - TMDL Modeling*
 - TMDL Implementation Plan*
 - Fecal Coliform Screening Parameter *
 - Fecal Coliform Inventory and Map (S050075-03 general permittees Appendix B B.5.2 document due to the department by March 31, 2022)
 - Fecal Coliform Source Elimination Plan (S050075-03 general permittees Appendix B document due to the department by October 31,2023)
- Sign and Submit form

Municipal Contact Information- Complete

Notice: Pursuant to s. NR 216.07(8), Wis. Adm. Code, an owner or operator of a Municipal Separate Storm Sewer System (MS4) is required to submit an annual report to the Department of Natural Resources (Department) by March 31 of each year to report on activities for the previous calendar year ("reporting year"). This form is being provided by the Department for the user's convenience for reporting on activities undertaken in each reporting year of the permit term. Personal information collected will be used for administrative purposes and may be provided to the extent required by Wisconsin's Open Records Law [ss. 19.31-19.39, Wis. Stats.]. **Note:** Compliance items must be submitted using the Attachments tab.

Municipality Information

Name of Municipality	Pewaukee, City				
Facility ID # or (FIN):	30726				
Updated Information:	Check to update mailing address information				
Mailing Address:	W240 N3065 Pewaukee Road				
Mailing Address 2:					
City:	Pewaukee				
State:	Wisconsin				
Zip Code:	53072 xxxxx or xxxxx-xxxx				

Primary Municipal Contact Person (Authorized Representative for MS4 Permit)

The "Authorized Representative" or "Authorized Municipal Contact" includes the municipal official that was charged with compliance and oversight of the permit conditions, and has signature authority for submitting permit documents to the Department (i.e., Mayor, Municipal Administrator, Director of Public Works, City Engineer).

Select to <i>create new</i> primary contact					
First Name:	Magdelene				
Last Name:	Wagner				
Select to <i>update</i> current contact information					
Title:	Director of Public Works				
Mailing Address:	W240 N3065 Pewaukee Road				
Mailing Address 2:					
City:	Pewaukee				
State:	WI				
Zip Code:	53072-4044 xxxxx or xxxxx-xxxx				
Phone Number:	262-691-0804 Ext: xxx-xxx-xxxx				
Email:	: wagner@pewaukee.wi.us				

Additional Contacts Information (Optional)

- 🗌 I&E Program
- ✓ IDDE Program
- □ IDD Plage n2el Pote 33 re Manual

Individual with responsibility for: (Check all that apply)	 Municipal-wide Water Quality Plan Ordinances Pollution Prevention Program Post-Construction Program Winter roadway maintenance 			
First Name:	Richard			
Last Name:	Wirtz			
Title:	Chief Engineer-Utili			
Mailing Address:	: W240 N3065 Pewaukee Road			
Mailing Address 2:				
City:	Pewaukee			
State:	<u>WI</u>			
Zip Code:	53072 xxxxx or xxxxx-xxxx			
Phone Number:	262-691-0804 Ext: xxx-xxx-xxxx			
Email:	wirtz@pewaukee.wi.us			

1. Does the municipality rely on another entity to satisfy some of the permit requirements?

Pollution Prevention

2. Has there been any changes to the municipality's participation in group efforts towards permit compliances (i.e., the municipality has added or dropped consortium membership)?

 \bigcirc Yes \odot No

Minimum Control Measures- Section 1: Complete

1. Public Education and Outreach

a. Complete the following information on Public Education and Outreach Activities related to storm water. Select the Delivery Mechanism that best describes how the topics were conveyed to your population. Use the Add Event to add additional entries.

Event Start Date	1/1/2020			
Project/Event Name	See Waukesh	a County Education Group	Spreadsheet for regional e	effort
Delivery Mechanism	<u>Other</u>			*Active
Topics Covered		Target Audience	Estimated People Reached (Optional)	Regional Effort (Optional)
 Illicit discharge detection and e Household hazardous waste di waste management/vehicle washir Yard waste management/pestifertilizer application Stream and shoreline managen Residential infiltration Construction sites and post-costorm water management Pollution prevention Green infrastructure/low impart development Other: 	sposal/pet ng icide and nent nstruction	 General Public Public Employees Residents Businesses Contractors Developers Industries Other 	<u>101 +</u>	• Yes O No

b. Brief explanation on Public Education and Outreach reporting. *Limit response to 250 characters and/or attach supplemental information on the attachments page.*

see attached Waukesha County Education Group Spreadsheet for regional effort

Form 3400-224 (09/20)

Minimum Control Measures - Section 2 : Complete

2. Public Involvement and Participation

a. <u>Permit Activities</u>. Complete the following information on Public Involvement and Participation Activities related to storm water. Select the Delivery Mechanism that best describes how the permit activities were conveyed to your population. Use the Add Event to add additional entries.

Event Start Date	1/1/2020				
Project/Event Name	Ongoing discussions regarding City storm water and erosion control requir				
Delivery Mechanism	<u>Other</u>				
Topics Covered	Target Audience	Reached (Ontional)	Regional Effort (Optional)		
	Page 23	01.93			

 MS4 Annual Report Storm Water Management Program Storm Water related ordinance Other: 	 General Public Public Employees Residents Businesses Contractors Developers 	<u>11-50</u>	○ Yes ● No
	 ☐ Industries ✓ Other 		

b. <u>Volunteer Activities</u>. Complete the following information on Public Involvement and Participation Activities related to storm water. Select the Delivery Mechanism that best describes how volunteer activities were conveyed to your population. Use the Add Event to add additional entries.

Event Start Date	5/1/2020				
Project/Event Name	WAV				
Delivery Mechanism	Stream monitoring				
Topics Covered	Target Audience	Estimated ((Optional)	People Reached	Regional Effort (Optional)	
Volunteer Opportunity	General Public	<u>11-50</u>		● Yes ○ No	
	Public Employees				
	Residents				
	Businesses				
	Contractors				
	Developers				
	☐ Industries				
	Other				
Event Start Date	7/1/2020				
Project/Event Name	Adopt A Drain				
Delivery Mechanism	Storm drain stenciling				
Topics Covered	Target Audience	Estimated ((Optional)	People Reached	Regional Effort (Optional)	
Volunteer Opportunity	✓ General Public	<u>51-100</u>		● Yes ○ No	
	Public Employees				
	Residents				
	Businesses				
	Developers				
	☐ Industries				
	Industries Other				
Event Start Date					
Event Start Date Project/Event Name	Other				
	Other 3/1/2020	24 of 9	3		

Topics Covered	Target Audience	Estimated People Reached (Optional)	Regional Effort (Optional)	
Volunteer Opportunity	General Public	<u>51-100</u>	● Yes ○ No	
	Public Employees			
	Residents			
	Businesses			
	Contractors			
	Industries			
	Other			
Event Start Date	5/5/2020			
Project/Event Name	Storm Water Workshop			
Delivery Mechanism	Presentation of Storm Water	Information		
Topics Covered	Target Audience	Estimated People Reached (Optional)	Regional Effort (Optional)	
Volunteer Opportunity	General Public	<u>101 +</u>	● Yes ○ No	
	Public Employees			
	Residents			
	Businesses			
	Contractors			
	✓ Developers			
	□ Industries			
	Other			

c. Brief explanation on Public Involvement and Participation reporting. *Limit response to 250 characters and/or attach supplemental information on the attachments page.* See attached City of Pewaukee Annual Report and 2020-2024 Waukesha County Summary Report

	•	•		•		
					For	m 3400-224 (09/20)
					101	111 3400 224 (03/20)
Min	imum Control Ma	asures - Section 3 : Con	nlata			
		asules - Section S. Con	ipiele			

3. Illicit Discharge Detection and Elimination

a.	How many total outfalls does the municipality have?	126	Unsure
b.	How many outfalls did the municipality evaluate as part of their routine ongoing field screening program?	20	Unsure
C.	From the municipality's routine screening, how many were confirmed illicit discharges?	0	Unsure
d.	How many illicit discharge complaints did the municipality receive?	1	Unsure
e.	From the complaints received, how many were confirmed illicit discharges?	0	Unsure
f.	Page 25 of 9	3	Unsure

	How many of the identified illicit discharges municipality eliminate in the reporting year routine screening and complaints)? (If the sum of 3.c. and 3.e. does not equal 3.f., please explain below.)	0				
 ^{g.} How many of the following enforcement mechanisms did the municipality use to enforce its illicit discharge ordinance? Check all that apply and enter the number of each used in the reporting year. ✓ Verbal Warning 						
	 Written Warning (including email) Notice of Violation 	0 0				
	Civil Penalty/ Citation	0				

Additional Information:

^{h.} Brief explanation on Illicit Discharge Detection and Elimination reporting. If you marked Unsure for any questions above, justify the reasoning. Limit response to 250 characters and/or attach supplemental information on the attachments page.

See attached City of Pewaukee Annual Report

				Form 3400-224 (09/20
N	1inimum Control Measures - Section 4 :	Complete		
4	. Construction Site Pollutant Control			
a.	How many total construction sites with of land disturbing construction activity point in the reporting year?		11	Unsure Unsure
b.	How many construction sites with one land disturbing construction activity did issue permits for in the reporting year?	Unsure Unsure		
c.	How many erosion control inspections complete in the reporting year?	389		
d.	What types of enforcement actions doe to compel compliance with the regulate apply and enter the number of each use No Authority	ck all that	Unsure Unsure	
	Verbal Warning			
	 Written Warning (including email) 	8		
	✓ Notice of Violation	4		
	 Civil Penalty/ Citation 			
	Stop Work Order	0		
	Forfeiture of Deposit			
	Other - Describe below	1		
Er	nforcement Conference	Page 26 of 93		

e. Brief explanation on Construction Site Pollutant Control reporting . *If you marked Unsure for any questions above, justify the reasoning. Limit response to 250 characters and/or attach supplemental information on the attachments page.*

See attached City of Pewaukee Annual Report

				Form 3400-224 (09/20)
Ν	1inimum Control Measures - Section 5 : Comp	olete		
5	. Post-Construction Storm Water Managemen	t		
a.	How many sites with new structural storm was management facilities* have received local ap *Engineered and constructed systems that are designed to pro- quality control such as wet detention ponds, constructed wetl basins, grassed swales, permeable pavement, catch basin sum	proval ? ovide storm water ands, infiltration	2	Unsure Unsure
b.	Does the municipality utilize privately owned a management facilities in its pollutant reduction	⊖ Yes ● No	Unsure Unsure	
c.	If Yes, How many privately owned storm wate	r	8	🗌 Unsure
	management facilities were inspected in the r Inspections completed by private land owners should be inclu- number.			
	 to compel compliance with the regulatory me apply and enter the number of each used in th No Authority Verbal Warning Written Warning (including email) Notice of Violation Civil Penalty/ Citation Forfeiture of Deposit 			
	Complete Maintenance	0		
	Bill Responsible Party	0		
	Other - Describe below			

 ^{e.} Brief explanation on Post-Construction Storm Water Management reporting. If marked 'Unsure' on any questions above, justify your reasoning. Limit your response to 250 characters and/or attach supplemental information on the attachments page.

The City's latest WinSLAMM analysis showed that road side swales alone provided a 31 percent reduction in TSS. If all of the wet detention facilities within the City were included the TSS reduction would be 59 percent.

6. Pollution Prevention Storm Water Management Facility Inspections Not Applicable a. Enter the total number of municipally owned or operated 8 Unsure	
structural storm water management facilities ?	
 b. How many new municipally owned storm water management facilities were installed in the reporting year ? 	
 ^{c.} How many municipally owned storm water management facilities 7 Unsure were inspected in the reporting year? 	
^{d.} What elements are looked at during inspections (250 character limit)?	
Embankments, outlets, vegetaion status, erosion, pretreatment, accumulated trash and debris, etc.	
e. How many of these facilities required maintenance? 4	
^{f.} Brief explanation on Storm Water Management Facility inspection reporting. If you marked Unsure for any questions above, justify the reasoning. Limit response to 250 characters and/or attach supplemental information on the attachments page.	
See attached City of Pewaukee Annual Report.	
Public Works Yards & Other Municipally Owned Properties (SWPPP Plan Review) 🗌 Not Applic	able
^{g.} How many municipal properties require a SWPPP? 1 Unsure	
 h. How many inspections of municipal properties have been conducted in the reporting year? 	
 i. Have amendments to the SWPPPs been made? ○ Yes ● No ○ Unsure 	
^{j.} If yes, describe what changes have been made. Limit response to 250 characters and/or attach supplemental information on the attachment page:	
^{k.} Brief explanation on Storm Water Pollution Prevention Plan reporting. <i>If you marked</i> <i>Unsure for any questions above, justify the reasoning. Limit response to 250</i> <i>characters and/or attach supplemental information on the attachments page.</i>	
See attached City of Pewaukee Annual Report	
Collection Services - Street Sweeping / Cleaning Program Not Applicable	
 Did the municipality conduct street sweeping/cleaning during the reporting year? ● Yes ○ No ○ Unsure 	
^{1.} Did the municipality conduct street sweeping/cleaning during the reporting year?	
 Did the municipality conduct street sweeping/cleaning during the reporting year? Yes O No O Unsure 	

	○ Yes - Explain frequer	ncy						
	O No - Explain							
	Not Applicable							
С	llection Services - Cat	ch Basin Su	mp Cleaning	g Program	🗌 Not App	olicable		
p.	Did the municipality conduct catch basin sump cleaning during the reporting year?							
q.	How many catch basi	n sumps we	ere cleaned	in the repo	orting year?	2	✓ Unsure	
r.	If known, how many	tons of mate	erial was co	llected?		26	🗌 Unsure	
s.	Does the municipality material?	y have a low	/ hazard exe	emption fo	r this	⊖Yes	No	
t.	If catch basin sump c in the pollutant loadi	-				-	•	
	⊖Yes- Explain frequen	су						
	○No - Explain							
	Not Applicable							
С	llection Services - Lea	f Collection	Program 星	Not Appl	icable			
	inter Road Manageme	-	-					
	ote: We are requesting in			nd the repo	rting vear ar	nswer the	hest vou can	
aa. ab.	How many lane-miles responsible for doing Provide amount of de Solids (tons) (ex. same	g snow and i e-icing prod	ce control? ucts used b		18 st winter se		🗌 Unsure	
	Product	Oct	Nov	Dec	Jan	Feb	Mar	
Sa		0	0	440	1000	800	0	
	Liquids (gallons) (ex.	brine)						
		Oct	Νον	Dec	Jan	Feb	Mar	
Br	ne	0	0	2268	4751	800	0	
ac.	 Was salt applying machinery calibrated in the reporting Yes No Unsure year? Have municipal personnel attended salt reduction strategy Yes No Unsure training in the reporting year? 							
au.	training in the report	ing year?						
au.	training in the report Training Date	• ·	Training Name		#	Attendanc	е	
au.	• .	• ·	Training Name		#	Attendanc	e	
au.	• .	nter Road Ma	anagement ro g. Limit resp	eporting. If y onse to 250	vou marked L	Jnsure fo	r any	
	Training Date Brief explanation on Wi questions above, justify	nter Road Ma the reasonin on on the att	anagement ro g. Limit resp achments pa	eporting. If y onse to 250	vou marked L	Jnsure fo	r any	

Internal (Staff) Education & Communication

^{af.} Has training or education been held for municipal or other ● Yes ○ No ○ Unsure personnel involved in implementing each of the pollution prevention program elements ?

If yes, describe what training was provided (250 character limit):

City engineering staff attended the Waukesha County Storm Water Workshop, NASECA Annual Conference, NASECA Construction Site Erosion Control Training and consultant sponsored MS4 seminars.

When: various times in 2020

How many attended: 3

^{ag.} Describe how the municipality has kept the following local officials and municipal staff aware of the municipal storm water discharge permit programs and its requirements.

Elected Officials

See Attached City of Pewaukee Annual Report

Municipal Officials

See Attached City of Pewaukee Annual Report

Appropriate Staff (such as operators, Department heads, and those that interact with public)

See attached City of Pewaukee Annual Report

^{ah.} Brief explanation on Internal Education reporting. If you marked Unsure for any questions above, justify the reasoning. Limit response to 250 characters and/or attach supplemental information on the attachments page.

See Attached City of Pewaukee Annual Report

Form 3400-224 (09/20)

Minimum Control Measures - Section 7 : Complete

7. Storm Sewer System Map

^{a.} Did the municipality update their storm sewer map this year?

○ Yes ● No ○ Unsure

If yes, check the areas the map items that got updated or changed:

- $\hfill\square$ Storm water treatment facilities
- □ Storm pipes
- □ Vegetated swales

Outfalls

Other - Describe below

^{b.} Brief explanation on Storm Sewer System Map reporting. *If you marked Unsure for an question for any questions above, justify the reasoning. Limit response to 250 characters and/or attach supplemental information on the attachments page.*

See attached City of Pewaukee Annual Report Page 30 of 93

Page 31 of 93

Final Evaluation - Complete

Fiscal Analysis

Complete the fiscal analysis table provided below. For municipalities that do not break out funding into permit program elements, please enter the monetary amount to your best estimate of what funding may be going towards these programs.

Annual	Budget	Budget	Source of Funds
Expenditure	Reporting Year	Upcoming	
Reporting Year		Year	
Element: Public E	Education and Out	reach	
1466	1500	1500	Storm water utility
Element: Public I	nvolvement and P	articipation	
1466	1500	1500	Storm water utility
	scharge Detection		
2610	1370	1430	Storm water utility
Elamont, Constru	uction Site Polluta	at Control	
			Other
75790	25161	36575	<u>Other</u>
Element: Post-Co	onstruction Storm	Water Manag	jement
30290	33161	44575	Other
Element: Pollutio	on Prevention		
639761	729226	824101	Storm water utility
Other (describe)			
			Select

Please provide a justification for a "0" entered in the Fiscal Analysis. Limit response to 250 characters.

Water Quality

a: Were there any known water quality improvements in the receiving waters to which the municipality's storm sewer system directly discharges to?

• Yes \bigcirc No \bigcirc Unsure If Yes, explain below:

Pewaukee River below the Village Dam was delisted (WBIC 771700)

b: Were there any known water quality degradation in the receiving waters to which the municipality's storm sewer system directly degree 20f 93

● Yes ○ No ○ Unsure If Yes, explain below: Pewaukee River above the Village Dam was 303d listed (WBIC 771800)

c: Have any of the receiving waters that the municipality discharges to been added to the impaired waters list during the reporting year?
● Yes ○ No ○ Unsure

d: Has the municipality evaluated their storm water practices to reduce the pollutants of concern?
● Yes ○ No ○ Unsure

Storm Water Quality Management

a . Has the r	nunicipality coi	mpleted or up	dated mode	eling in the	reporting yea	ar (relating	to developed
urban area	performance s	tandards of s.	NR 151.13(2)(b)1., Wis	s. Adm. Code)? 🔿 Yes	● No

b. If yes, enter percent reduction in the annual average mass discharging from the entire MS4 to surface waters of the state as compared to implementing no storm water management controls:

Total suspended solids (TSS) Total phosphorus (TP)

Additional Information

Based on the municipality's storm water program evaluation, describe any proposed changes to the municipality's storm water program. *If your response exceeds the 250 character limit, attach supplemental information on the attachments page.*

See attached City of Pewaukee Annual Report

Requests for Assistance on Understanding Permit Programs

Would the municipality like the Department to contact them about providing more information on understanding any of the Municipal Separate Storm Sewer Permit programs?

- Please select all that apply:
- □ Public Education and Outreach
- Public Involvement and Participation
- □ Illicit Discharge Detection and Elimination
- Construction Site Pollutant Control
- □ Post-Construction Storm Water Management
- □ Pollution Prevention
- □ Storm Water Quality Management
- □ Storm Sewer System Map
- □ Water Quality Concerns
- Compliance Schedule Items Due
- □ MS4 Program Evaluation

Required Attachments and Supplemental Information

Any other MS4 program information for inclusion in the Annual Report may be attached on here. Use the Add Additional Attachments to add multiple documents.

Upload Required Attachments (15 MB per file limit) - <u>Help reduce file size and trouble shoot file uploads</u> *Required Item

Note: To replace an existing file, use the 'Click here to attach file ' link or press the to delete an item.

Attach - Other Supporting Documents		
AR_EO		
File Attachment	2020-ms4-reporting.xlsx	
AR IP		
File Attachment	2020-2024MS4PublicEducationandOutreachPlan.pdf	
AR Other		
File Attachment	20210331_CityofPewaukeeAnnualReportfor2020.pdf	

(To remove items, use your cursor to hover over the attachment section. When the drop down arrow appears, select remove item)

Attach - Permit Compliance Documents

(To remove items, use your cursor to hover over the attachment section. When the drop down arrow appears, select remove item)

Steps to Complete the signature process

- 1. Read and Accept the Terms and Conditions
- 2. Press the Submit and Send to the DNR button

NOTE: For security purposes all email correspondence will be sent to the address you used when registering your WAMS ID. This may be a different email than that provided in the application. For information on your WAMS account click <u>HERE</u>.

Terms and Conditions

Certification: I hereby certify that I am an authorized representative of the municipality covered under Pewaukee, City MS4 Permit for which this annual report or other compliance document is being submitted, and that the information contained in this submittal and all attachments were gathered and prepared under my direction or supervision. Based on my inquiry of the person or persons under my direction or supervision involved in the preparation of this document, to the best of my knowledge, the information is true, accurate, and complete. I further certify that the municipality's governing body or delegated representatives have reviewed or been apprised of the contents of this annual report. I understand that Wisconsin law provides severe penalties for submitting false information.

Signee (must check current role prior to accepting terms and conditions)

• Authorized municipal contact using WAMS ID.

○ Delegation of Signature Authority (Form 3400-220) for agent signing on the behalf of the authorized municipal contact.

○ Agent seeking to share this item with authorized municipal contact (authorized municipal contact must get WAMS id and complete signature).

Nam	Magdelene Wagner	
Titl	e: Director of Public Works/City Engineer	
Authorized Signature. ✓ I accept the above terms and conditions.	Signed by : i:0#.f wamsmembership cityofpewaukee on 2021-03-31T15:39:01 You have already signed and submitted this application to the DNR. Please <u>contact</u> <u>the Wisconsin DNR</u> for assistance.	

After providing the final authorized signature, the system will send an email to the authorized party and any agents. This email will include a copy to the final read only version of this application.

Item B

Draft Post-Construction Site Storm Water Management Program and Inspection Forms

City of Pewaukee Post-Construction Storm Water Management Program

Introduction

The City of Pewaukee is required under its WPDES permit to continue to implement and enforce its program to control the quantity and quality of discharges from areas of new development and redevelopment. The City is also required to establish measurable goals for its post construction storm water management program. More specifically, the City's program at a minimum is required to:

- Enforce the applicability and jurisdiction of Chapter 19 of the Municipal Code.
- Enforce the design criteria, standards and specifications for the design and implementation of postconstruction storm water management control practices which meet or exceed the criteria of those approved by the Department of Natural Resources.
- Review and approve plans that meet or exceed the City's Post Construction Storm Water Management Ordinance (Chapter 19 of the Municipal Code), the City of Pewaukee Technical Standards and the Conservation Practice Standards approved by the Department of Natural Resources.
- Update and enforce the City's Post Construction Storm Water Management Ordinance to meet or exceed the requirements of NR 151.121-NR 151.128 and 151.241-NR 151.249 of the Wisconsin Administrative Code.
- Enforce storm water management plan requirements which meet or exceed those contained in NR 216.47 of the Wisconsin Administrative Code.
- Enforce the permitting requirements, procedures and fees established in Chapter 19 of the Municipal Code.
- Establish written procedures to track and enforce the long-term maintenance of storm water management facilities implemented to meet the applicable post-construction performance standards of NR 216 and NR 151 of the Wisconsin Administrative Code and Chapter 19 of the Municipal Code.

The purpose of this document is to memorialize the aspects, procedures, forms and records of the City's program to ensure adequate and consistent regulation, inspection and enforcement of the City's ordinance in compliance with the City's WPDES permit.

Ordinance

The City is granted authority to adopt a post-construction storm water management ordinance under §62.234 Wis. Stats. The City Engineer or designee is granted the authority by the Common Council to administer and enforce the provisions of the ordinance. Portions of the ordinance have been revised from time to time to comply with the applicable provisions of NR 216 and NR 151 as required under the City's WPDES permit.

The purpose and intent of the post-construction storm water management ordinance is to establish requirements for post-construction runoff that will minimize the amount of sediment and other pollutants carried by runoff to waters of the state and that will diminish the threats to public health, safety, welfare and the aquatic environment. Specific purposes of the ordinance are to:

• Further the maintenance of safe and healthful conditions

P:\City\NR 216 Permit\Storm Water Managment Program\20200430_Draft City of Pewaukee_Post-Construction Storm Water Management Program.docx

- Prevent and control water pollution.
- Prevent and control the adverse effects of storm water.
- Control the exceedance of the safe capacity of existing drainage facilities and receiving water bodies.
- Prevent undue channel erosion and control increases in the scouring and transportation of particulate matter.
- Minimize the amount of pollutants discharged from the municipal separate storm sewer system to protect waters of the state.
- Prevent conditions that endanger downstream property.

The ordinance applies to any post-construction site after final stabilization that had one or more acres of land disturbing construction activity. The post-construction storm water management ordinance does not apply to:

- A post-construction site with less than 10 percent connected imperviousness based on the area of land disturbance, provided the cumulative area of all impervious surfaces is less than one acre. However, the exemption in this paragraph does not include an exemption from the protective area standard in s. NR 151.125 Wis. Adm. Code and this ordinance.
- Agricultural facilities and practices.
- Underground utility construction but not including the construction of above ground structures associated with utility construction.

Any person or entity subject to the post-construction storm water management requirements of the City's ordinance must submit an application for a permit accompanied by a storm water management plan and maintenance agreement. The storm water management plan shall be prepared to meet the requirements of Section 19.09 and 19.12 of the City's Municipal Code. The maintenance plan shall be prepared to meet the requirements of Section 19.13 of the City's Municipal Code. A copy of the of the permit application is contained in Appendix A and a copy of the Chapter 19 of the Municipal Code (Construction Site Erosion Control, Post-Construction Storm Water Management, and Illicit Discharge Ordinance) is contained in Appendix B.

Plan Review

The storm water management plan, maintenance plan and associated grading plans and details are subject to review by the City's Engineering Staff or Engineering Consultant. Best Management Practices (BMP's) incorporated into the plans are reviewed for conformance with the design criteria, standards and specifications of:

- The design guidance and technical standards identified or developed by the Wisconsin Department of Natural Resources under subchapter V of NR 151, Wis. Administrative Code.
- Other such standards approved by the City Engineer or designee.
- The City of Pewaukee Technical Standards (contained in Appendix C).

Storm water management plans and practices shall comply with the performance standards identified in Section 19.09 of the Municipal Code. In general storm water management plans will: employ practices designed, installed and maintained to control total suspended solids in runoff from the post-construction site; to maintain or reduce the peak rate of runoff from the post-developed site as compared to pre-settlement conditions; design, install and maintain practices to infiltrate runoff to the maximum extent practicable; enforce wetland protective areas; and require BMP's for fueling and vehicle maintenance areas. The

P:\City\NR 216 Permit\Storm Water Managment Program\20200430_Draft City of Pewaukee_Post-Construction Storm Water Management Program.docx

Page 39 of 93

minimum plan requirements are identified in Section 19.12 and the minimum maintenance agreement requirements are identified in Section 19.13 of the Municipal Code. The City has a standard storm water management practices maintenance agreement to be used as a template. Approved agreements are to be signed by both the developer and the City and recorded at the Waukesha County Register of Deeds. A copy of the recorded agreement should be provided to the City for its files.

The Waukesha County Register of Deeds requires documents submitted for recording be legible and reproducible. The maximum page size of the documents is to be either 8.5x11 or 8.5x14 inches. The clarity of full-size drawings which are reduced to fit on the page sizes acceptable to the County is often poor. Should the County reject the recording the agreement for not being legible or reproducible, the City can provide a certification to the County stating the City has legible copies of all figures within the agreement (generally full-size documents). Care must be taken when providing the certification that any full-size figures provided are exact copies of those in the agreement. All copies of the agreements and associated figures shall be kept in a central and easily accessible location and must be maintained for the life of the practices. Currently, that location is within the office of the Chief Engineer-Utilities.

Submitted storm water management plans and maintenance agreements which do meet the minimum plan requirements, performance standards or technical and design criteria shall not be accepted. Plans and maintenance agreements which are not accepted will be temporarily retained until such time as the development has met the requirements of the City. A letter documenting the plan deficiencies (see sample letter in Appendix D) will be provided to the applicant and their engineer. Plans and maintenance agreements meeting the requirements of the Municipal Code will be accepted and a post construction storm water permit and letter issued to the applicant (see sample letter and permit in Appendix E). Only accepted plans and maintenance agreements will be retained for City files. Previously submitted plans and agreements will be disposed of once the permits have been issued.

Permitting

Post construction storm water management permits require the permittee or responsible party to generally: design and install the storm water management measures in accordance with the accepted plans; notify the City Engineer before commencing work in conjunction with the storm water management plan and after completion of the practices; complete the storm water management practice installations; provide a certified as-built by a licensed professional engineer documenting the completed installations are in accordance with the accepted plans and pass an inspection by the City Engineer; Notify the City Engineer of any significant modifications intended to be made to the accepted storm water management plan; and to maintain all installed storm water management practices consistent with the terms of the maintenance agreement. Permits for post construction site storm water management are valid from the date of issuance through the date the City Engineer notifies the permittee that all practices have passed a final inspection.

Long Term Maintenance and Inspection of Permitted Facilities

Enforcement

Filing, Records Retention and Database

City of Pewaukee Public Works Bioretention Pond Inspection Report

<u>Facility ID:</u> <u>Facility/Site Contact Person:</u> <u>Mailing Address:</u> <u>Email Address:</u> <u>Phone Number:</u>	Location:	
Name of Person Conducting the Inspection:	Inspection Date:	
Tempertaure:°F	Inspection Time:	
Weather Conditions: Sunny Partly Sunny Partly	/ Cloudy Cloudy Rain	
□Freezing Rain or Sleet □Snow	□Windy □Other:	
Rain in Last 48 Hours 🗆 Yes 🗆 No 🗆 N/A 👘 If yes:	Amount in inches: and timing:	
	Standing water present: 🗆 Yes 🗆 No 🗆 N/A	
	If yes, describe color, odor, and sheen:	
Protroctments [] Vegetated Filter Strip [] Swels [] Fe		
Pretreatment: Vegetated Filter Strip Swale Fo Plan Available: As-Built Site No plan available		
Other Site Conditions:		
Pretreatment		
1. Vegetation has accumulated	□ Yes □ No □ N/A	
2. Sediment has accumulated	□ Yes □ No □ N/A	
3. Debris/Trash has accumulated	□ Yes □ No □ N/A	
4. Erosion/Undercutting	□ Yes □ No □ N/A	
5. Bypassing flow	🗆 Yes 🗆 No 🗔 N/A	
Embankments		
1. Visible cracks or sinkholes	□ Yes □ No □ N/A	
Unwanted trees or woody vegetation	□ Yes □ No □ N/A	
3. Animal burrows	□ Yes □ No □ N/A	
 Vegetation inadequately maintained 	□ Yes □ No □ N/A	
5. Unhealthy vegetative cover	□ Yes □ No □ N/A	
6. Seepage	□ Yes □ No □ N/A	
7. Sinkholes	□ Yes □ No □ N/A	

Inlets	
1. Vegetation has accumulated	□ Yes □ No □ N/A
2. Sediment has accumulated	🗆 Yes 🗆 No 🗆 N/A
3. Debris/Trash has accumulated	🗆 Yes 🗆 No 🗆 N/A
4. Erosion/Undercutting	🗆 Yes 🗆 No 🗆 N/A
5. Poor structural condition	🗆 Yes 🗆 No 🗆 N/A
Vegetation	
1. Undesirable vegetation	□ Yes □ No □ N/A
2. Desired vegetation is dying or receding due to climate,	□ Yes □ No □ N/A
competition or disease	
Bioretention Area	
1. Sediment has accumulated	□ Yes □ No □ N/A
2. Debris/Trash has accumulated	□ Yes □ No □ N/A
3. Erosion/undercutting	□ Yes □ No □ N/A
4. Animal burrows or sinkholes are present	□ Yes □ No □ N/A
5. Topsoil is covered with sediment	🗆 Yes 🗆 No 🗆 N/A
6. Mulch is compacted	□ Yes □ No □ N/A
Outlets and Overflow Structures	
1. Sediment has accumulated	□ Yes □ No □ N/A
2. Debris/Trash has accumulated	🗆 Yes 🗆 No 🗆 N/A
3. Erosion/Undercutting	🗆 Yes 🗆 No 🗆 N/A
4. Poor structural condition	🗆 Yes 🗆 No 🗆 N/A
5. Visible leaks/joint failure	🗆 Yes 🗆 No 🗆 N/A
6. Insufficient depth for pond to function correctly	🗆 Yes 🗆 No 🗆 N/A
Emergency Spillway	
1. Erosion/Undercutting	□ Yes □ No □ N/A
2. Vegetation has accumulated	□ Yes □ No □ N/A
3. Spillway obstructed	□ Yes □ No □ N/A
Miscellaneous Feature	
1. Restricted access	□ Yes □ No □ N/A
2. Lack of maintenance	$\Box \text{ Yes } \Box \text{ No } \Box \text{ N/A}$
3. Issues with additional features	$\Box \text{ Yes } \Box \text{ No } \Box \text{ N/A}$
4. Unapproved modification	$\Box \text{ Yes } \Box \text{ No } \Box \text{ N/A}$

Attached Pictures or Sketches:

Wet Pond Inspection Report 3

Inspection Results:
Pass
The dry pond is operating without observed issues.
□ Pass with conditions
The dry pond is operating as intended. Issues exist and should be addressed; however they do not currently prevent the pond from operating as intended.
🗆 Fail
Issues exist and are preventing the dry pond from operating as intended.
Inspector certifies accuracy of information:
Inspector Signature:
Date of Inspection:
Wet Pond Inspection Report 4
Page 44 of 93

City of Pewaukee Public Works Dry Pond Inspection Report

<u>Facility ID:</u> <u>Facility/Site Contact Person:</u> <u>Mailing Address:</u> <u>Email Address:</u> <u>Phone Number:</u>	<u>Location:</u>
Name of Person Conducting the Inspection:	Inspection Date:
Tempertaure:°F	Inspection Time:
Weather Conditions: Sunny Partly Sunny Partly	
□Freezing Rain or Sleet □Snow	□Windy □Other:
Rain in Last 48 Hours 🗆 Yes 🗆 No 🗆 N/A	If yes, amount in inches: and timing:
Pretreatment: 🗆 Vegetated Filter Strip 🗆 Swale 🗆 Fo	rebay 🗆 None 🗆 Other:
Plan Available: 🗆 As-Built 🔲 Site 🗀 No plan available	
Other Site Conditions:	
Pretreatment	
1. Vegetation has accumulated	□ Yes □ No □ N/A
2. Sediment has accumulated	□ Yes □ No □ N/A
3. Debris/Trash has accumulated	□ Yes □ No □ N/A
4. Erosion/Undercutting	□ Yes □ No □ N/A
5. Bypassing flow	□ Yes □ No □ N/A
Embankments	
1. Visible cracks or sinkholes	□ Yes □ No □ N/A
2. Unwanted trees or woody vegetation	□ Yes □ No □ N/A
3. Animal burrows	□ Yes □ No □ N/A
Vegetation inadequately maintained	🗆 Yes 🗆 No 🗔 N/A
5. Unhealthy vegetative cover	□ Yes □ No □ N/A
6. Seepage	□ Yes □ No □ N/A
Inlets	
1. Vegetation has accumulated	□ Yes □ No □ N/A
2. Sediment has accumulated	🗆 Yes 🗆 No 🗔 N/A
3. Debris/Trash has accumulated	□ Yes □ No □ N/A
4. Erosion/Undercutting	□ Yes □ No □ N/A
5. Displacement of filter fabric	□ Yes □ No □ N/A
6. Poor structural condition	□ Yes □ No □ N/A
	· · · · ·
	Dry Pond Inspection Report 1

Basin or Bowl Area		
1. Vegetation has accumulated	□ Yes □ No □ N/A	
2. Sediment has accumulated	$\Box \text{ Yes } \Box \text{ No } \Box \text{ N/A}$	
3. Debris/Trash has accumulated	□ Yes □ No □ N/A	
4. Erosion/Undercutting	\Box Yes \Box No \Box N/A	
5. Animal burrows or sinkholes	$\Box \text{ Yes } \Box \text{ No } \Box \text{ N/A}$	
6. Standing water (at least five days after most recent storm)	$\Box \text{ Yes } \Box \text{ No } \Box \text{ N/A}$	
Outlets and Overflow Structures		
1. Sediment has accumulated	□ Yes □ No □ N/A	
2. Debris/Trash has accumulated		
3. Erosion/Undercutting	□ Yes □ No □ N/A	
4. Poor structural condition	□ Yes □ No □ N/A	
5. Visible leaks/joint failure	□ Yes □ No □ N/A	
6. Displacement of filter fabric	□ Yes □ No □ N/A	
Emergency Spillway		
1. Erosion/Undercutting	□ Yes □ No □ N/A	
2. Vegetation has accumulated	□ Yes □ No □ N/A	
3. Spillway obstructed	□ Yes □ No □ N/A	
	· · · · · · · · · · · · · · · · · · ·	
Miscellaneous Feature		
1. Restricted access	🗆 Yes 🗆 No 🗆 N/A	
2. Lack of maintenance	🗆 Yes 🗆 No 🗆 N/A	
3. Issues with additional features	□ Yes □ No □ N/A	
4. Unapproved modification	□ Yes □ No □ N/A	
Additional Notes		
	Dry Pond Inspection Report 2	
Page 46 of 93		

Attached Pictures or Sketches:

Dry Pond Inspection Report 3



Inspection	Results:
------------	-----------------

Pass

The dry pond is operating without observed issues.

□ Pass with conditions

The dry pond is operating as intended. Issues exist and should be addressed; however they do not currently prevent the pond from operating as intended.

Page 48 of 93

🗆 Fail

Issues exist and are preventing the dry pond from operating as intended.

Inspector certifies accuracy of information:

Inspector Signature: _____

Date of Inspection: _____

Dry Pond Inspection Report 4

City of Pewaukee Public Works Infiltration Pond Inspection Report

<u>Facility ID:</u> <u>Facility/Site Contact Person:</u> <u>Mailing Address:</u> <u>Email Address:</u> <u>Phone Number:</u>	<u>Location:</u>
Name of Person Conducting the Inspection:	Inspection Date:
Tempertaure:°F	Inspection Time:
Weather Conditions: Sunny Partly Sunny Partly	
□Freezing Rain or Sleet □Snow	
Rain in Last 48 Hours 🗆 Yes 🗆 No 🗆 N/A 🛛 If yes:	Amount in inches: and timing:
	Standing water present: Yes No N/A
	If yes, describe color, odor, and sheen:
Pretreatment: Vegetated Filter Strip Swale Fc	
Plan Available: As-Built Site No plan available	
Other Site Conditions:	
Pretreatment	
1. Vegetation has accumulated	□ Yes □ No □ N/A
2. Sediment has accumulated	□ Yes □ No □ N/A
3. Debris/Trash has accumulated	□ Yes □ No □ N/A
4. Erosion/Undercutting	□ Yes □ No □ N/A
5. Bypassing flow	□ Yes □ No □ N/A
	· · · · · ·
Embankments	
1. Visible cracks or sinkholes	□ Yes □ No □ N/A
Unwanted trees or woody vegetation	□ Yes □ No □ N/A
3. Animal burrows	□ Yes □ No □ N/A
 Vegetation inadequately maintained 	□ Yes □ No □ N/A
5. Unhealthy vegetative cover	□ Yes □ No □ N/A
6. Seepage	□ Yes □ No □ N/A
7. Sinkholes	□ Yes □ No □ N/A

Inlets	
1. Vegetation has accumulated	□ Yes □ No □ N/A
2. Sediment has accumulated	🗆 Yes 🗆 No 🗆 N/A
3. Debris/Trash has accumulated	🗆 Yes 🗆 No 🗆 N/A
4. Erosion/Undercutting	🗆 Yes 🗆 No 🗆 N/A
5. Poor structural condition	🗆 Yes 🗆 No 🗆 N/A
Vegetative Basin	
1. Undesirable non-native vegetation	□ Yes □ No □ N/A
2. Desired vegetation is dying or receding	□ Yes □ No □ N/A
3. Debris/Pollution/Trash has accumulated	\Box Yes \Box No \Box N/A
4. Shoreline erosion	□ Yes □ No □ N/A
5. Outfall erosion	□ Yes □ No □ N/A
6. Pond walls in poor condition	□ Yes □ No □ N/A
7. Encroachment into easement or pond area by other activities	□ Yes □ No □ N/A
Outlets and Overflow Structures 1. Sediment has accumulated	□ Yes □ No □ N/A
2. Debris/Trash has accumulated	
3. Erosion/Undercutting	□ Yes □ No □ N/A □ Yes □ No □ N/A
4. Poor structural condition	□ Yes □ No □ N/A
5. Visible leaks/joint failure	$\Box \text{ Yes } \Box \text{ No } \Box \text{ N/A}$
6. Inappropriate depth for pond to function correctly	$\Box \text{ Yes } \Box \text{ No } \Box \text{ N/A}$
Emergency Spillway	
1. Erosion/Undercutting	□ Yes □ No □ N/A
2. Vegetation has accumulated	□ Yes □ No □ N/A
3. Spillway obstructed	□ Yes □ No □ N/A
Miscellaneous Feature	
1. Restricted access	Yes No N/A
2. Lack of maintenance	Yes No N/A
3. Issues with additional features	□ Yes □ No □ N/A
4. Unapproved modification	Yes No N/A
5. Invasive species	□ Yes □ No □ N/A

Wet Pond Inspection Report 2

Attached Pictures or Sketches:

Wet Pond Inspection Report 3

Page 52 of 93

City of Pewaukee Public Works Wet Pond Inspection Report

Facility ID:	Location:
Facility/Site Contact Person:	
Mailing Address:	
Email Address:	
Phone Number:	
Name of Person Conducting the Inspection:	Inspection Date:
Tempertaure:°F	Inspection Time:
Weather Conditions: Sunny Partly Sunny Partly	
□ Freezing Rain or Sleet □ Snow	
Rain in Last 48 Hours 🗆 Yes 🗆 No 🗆 N/A	If yes, amount in inches: and timing:
Pretreatment: 🗆 Vegetated Filter Strip 🗆 Swale 🗆 Fo	orebay 🗆 None 🗆 Other:
Plan Available: 🗆 As-Built 🔲 Site 🗆 No plan available	
Other Site Conditions:	
Pretreatment	
1. Vegetation has accumulated	□ Yes □ No □ N/A
2. Sediment has accumulated	🗆 Yes 🗆 No 🗔 N/A
3. Debris/Trash has accumulated	🗆 Yes 🗆 No 🗔 N/A
4. Erosion/Undercutting	🗆 Yes 🗆 No 🗔 N/A
5. Bypassing flow	🗆 Yes 🗆 No 🗔 N/A
Embankments	
1. Visible cracks or sinkholes	🗆 Yes 🗆 No 🗔 N/A
2. Unwanted trees or woody vegetation	🗆 Yes 🗆 No 🗔 N/A
3. Animal burrows	🗆 Yes 🗆 No 🗔 N/A
4. Vegetation inadequately maintained	🗆 Yes 🗆 No 🗔 N/A
5. Unhealthy vegetative cover	🗆 Yes 🗆 No 🗔 N/A
6. Seepage	🗆 Yes 🗆 No 🗔 N/A

Inlets	
1. Vegetation has accumulated	□ Yes □ No □ N/A
2. Sediment has accumulated	□ Yes □ No □ N/A
3. Debris/Trash has accumulated	🗆 Yes 🗆 No 🗆 N/A
4. Erosion/Undercutting	🗆 Yes 🗆 No 🗆 N/A
5. Displacement of filter fabric	□ Yes □ No □ N/A
6. Poor structural condition	🗆 Yes 🗆 No 🗆 N/A
Permanent Pool	
1. Undesirable vegetation	□ Yes □ No □ N/A
2. Sediment has accumulated	□ Yes □ No □ N/A
3. Debris/Pollution/Trash has accumulated	□ Yes □ No □ N/A
4. Shoreline erosion	□ Yes □ No □ N/A
5. Outfall erosion	□ Yes □ No □ N/A
6. Pond walls in poor condition	□ Yes □ No □ N/A
7. Encroachment into easement or pond area by other activities	□ Yes □ No □ N/A
Outlets and Overflow Structures	
1. Sediment has accumulated	
2. Debris/Trash has accumulated	Yes No N/A
3. Erosion/Undercutting	Yes No N/A
4. Poor structural condition	□ Yes □ No □ N/A
5. Visible leaks/joint failure	Yes No N/A
6. Displacement of filter fabric	□ Yes □ No □ N/A
Emergency Spillway	
1. Erosion/Undercutting	
2. Vegetation has accumulated	
3. Spillway obstructed	□ Yes □ No □ N/A
Missellensous Fosturo	
Miscellaneous Feature 1. Restricted access	
2. Lack of maintenance	
2. Lack of maintenance 3. Issues with additional features	
4. Unapproved modification	□ Yes □ No □ N/A

Wet Pond Inspection Report 2

Attached Pictures or Sketches:

Wet Pond Inspection Report 3

Inspection Results:
Pass
The dry pond is operating without observed issues.
□ Pass with conditions
The dry pond is operating as intended. Issues exist and should be addressed; however they do not currently prevent the pond from operating as intended.
Fail
Issues exist and are preventing the dry pond from operating as intended.
Inspector certifies accuracy of information:
Inspector Signature:
Date of Inspection:
Wet Pond Inspection Report 4

Item C

Winter Road Management Summary Tables

	Other Information	Started at 2 am ended 7 am	Rain at 4:30 am ended 7:30 am	Rain @ 4:00 am switched to snow I"	1" overnight with 40 mph winds	10:00 am start 6" total Ended 3:00 am o the 13th	5:30am start snow @6:00am done @ noon	3"Started @ noon ended @ 7 P.M	Freezing Rain started @4:30 PM	Freezing rain throught the the night	10 PM start ended 3AM 1"	Pre- storm Pre- Wet	11 AM start 5PM	Pre- storm Pre- Wet	3 PM start 1 AM ended	5AM start 8Am ended 2"	Pre-storm Pre- Wet	Started 8PM ended 6 Am on 24th	Pre- storm Pre- Wet	Starred at 2 pm and ended at 6 pm	
	Hours of Post-Event Clean-Up		0	0	0	24	12	0	0	0	0		0		0	0		24		0	<u>81</u>
	24 Drivers/# of Drivers/#	7	8	8	8	8	8	8	8	8	8		8		8	8		8		8	Number of Entries
Usage ee	(worked) Hours of Event		32	30	32	52	64	06	24	24	32		64		32	31		32		29	<u>596</u>
Road Salt / Deicers Usage City of Pewaukee 2011-2012	Precipitation Amount (inches)	1	Ice	1	1	6	4	3	Ice	Ice	1		3		1	2		4		5	Total event hours worked
Ro	Pavement Temperature Range during event (°F)																				
	sgnas Prature Range Air Temperature Range during event (°F)	23 to28	28 to 30	30 to 32	19	32 to 15	29 to 23	15 to 20	32	32	26		32 to 18		29	31		30		30	
	do nuond of Product Used (Tons)	80	80	80	90	220	160	120	60	60	80		120		70	80		120		120	1540
	Product Used (hnrsAlfra=xim)	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt		Salt		Salt	Salt		Salt		Salt	Total Salt Used (tons)
	Salt Brine Used (gal)	450	450	450	450	1200	1000	800	400	500	450	1100	450	1050	500	450	1425	925	1450	700	14200
	ζήνης	Plow	Salting Only	Plow	Plow	Plow	Plow	Plow	Salting Only	Salting Only	Plow	Pre-Wetting	Plow	Pre-Wetting	Plow	Plow	Pre-Wetting	Plow	Pre-Wetting	Plow	Total Brine Used (gal)
	Date(s) of Event	17-Dec-11	29-Dec-11	1-Jan-12	2-Jan-12	12-Jan-12	17-Jan-12	20-Jan-12	22-Jan-12	23-Jan-12	28-Jan-12		0-Feb-12	O 3-Feb-12	A ^{4-Feb-12}	G -Feb-12	B -Feb-12	Q ^{4-Feb-12}	A-Mar-12	6 -Mar-12	

P:\City\NR 216 Permit\Winter Management De-icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xlsx

	Other Information	Pre- storm Pre- Wet	Pre-storm Pre- Wet	streaded at 6 mm	otar tea at 2 pm ana enaea at 0 pm Pre- ciorm Pre- Wet	1 am started with 3 incluse hy morning: cwitched to win 1 30 incluse	r an our can me o needed by normals, on concert to rain 1.30 mento	7 am start 1 inch	5:30 start 1 inch	All day snow 1 inch	4 pm start 0.5 inch salt run	I inch overnight	Had to re-plow and salt; roads wouldn't melt	Light dusting; temperatures dropping	1 inch of snow turned to rain	Roads refroze with rain turning to ice	Rain changing to ice; no accumulation	Snow, 2 inches by mid-morning	1 inch of additional snow with full clean-up	Light dusting with temperatures dropping and high winds	10 pm snow began; snow ends at 5 am	start	Clean up from morning run	Started at 11 am and ended at 1 pm	Snow started at 11 am and ended at 11 pm	Clean up from 2/7	Pre-storm Pre-wet/3 inches of snow	Light rain turning to ice	Light snow overnight	0.5 inch rain changed over to snow	Second run for storm shish and ice.	2 am start with 5 inches ending be 6 am	Clean up from storm	Pre-storm Pre-wet	Start of Storm	Beginning of clean up	Finished clean up	Dusting overnight	9 am snow started; out until rush hour
	Hours of Post-Event Clean-Up		Pre-	0 Start		0 1 am							0 Had 1		0 I incl		0 Rain			0 Light			0 Clean	0 Starte	0 Snow	0 Clean	0 Pre-s	0 Light	0 Light	0 0.5 in	0 Secon	0 2 am	0 Clean	Pre-s.	0 Start	0 Begin	0 Finish	0 Dusti	0 9 am
	‡ of Drivers/# of Trucks			0		6	6	6	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	2	8	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~	7	8	8	8	8	8	8	8	6		8	6	6	6	6	7	6	6	6	8		6	6	6	8	6
	Hours of Event (worked)			45	P	100	36	27	32	27	24	30	32	20	28	32	16	32	32	24	36	36		36	36	54	27	24	24	36	40	36	24		27	36	48	20	36
2012-2013	Precipitation Amount (inches)			6	1	6	. 6	1	1	1	0.5	1	0	0.5	1	Ice	Ice	2	1	0.5	2	2		2	7		m	Ice	0.5	2		5			7			0.5	3
	Pavement Temperature Pange during event (°F)																																						
3	Air Temperature Rang during event (P)			32 to 34		32 to 36	28	29	27	26	31	23	16	14	28	32	33	33	28	16	13	10	8	17	28	20	22	33	13	16	16	30	32		31	32	32	32	30
	toudat of Product Used (Tons)			140		120	120	100	110	110	120	110	06	06	140	150	150	120	100	120	100	100	80	80	150	80	60	60	70	06	06	06	60		60	36	45	40	50
	Product Used (baszUlsz=xim)			Salt		Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt
	(lag) bəzÜ ərin& İlaZ	1200	1375	500	650	600	500	500	500	600	400	500	350	350	450	500	500	500	400	250	0	0	0	500	700	500	672	500	450	500	400	500	40	1497	500	500	500	500	500
	γίητογ	Pre-Wetting	Pre-Wetting	Plow	Pre-Wetting	Plow	Plow	Plow	Plow	Plow	Salting Only	Plow	Plow	Salting Only	Plow	Salting Only	Salting Only	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Salting Only	Plow	Plow	Plow	Plow	Pre-Wetting	Plow	Plow	Plow	Salting Only	Plow
	Jate(s) of Event	7-Dec-12	18-Dec-12	18-Dec-12	19-Dec-12	20-Dec-12	21-Dec-12	28-Dec-12	29-Dec-12	29-Dec-12	5-Jan-13		O ^{13-Jan-13}	6 23-Jan-13	D ^{27-Jan-13}	G ^{38-Jan-13}	6 0-Jan-13	0 ^{30-Jan-13}	3 0-Jan-13	6 1-Jan-13	$\mathbf{g}^{2-\mathrm{Feb-13}}$	4-Feb-13	4-Feb-13	5-Feb-13	7-Feb-13	8-Feb-13	13-Feb-13	14-Feb-13	15-Feb-13	19-Feb-13	19-Feb-13	22-Feb-13	22-Feb-13	25-Feb-13	26-Feb-13	27-Feb-13	27-Feb-13	28-Feb-13	5-Mar-13

Road Salt / Deicers Usage City of Pewaukee 2012-2013

P:\City\NR 216 Permit\Winter Management De-icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xisx

	Other In	3 am start total cleanup	Slush run	Rain chaging to ice; no accumulation	Pre-storm Pre-wet	Light dusting	Started at 8 am and done at 5 pm	Temps dropped overnight; spotty ice
	Hours of Post-Event Clean-Up		0	0		0	0	0
	24 Drivers/# of Drivers	6	8	6		6	6	6
lkee	Hours of Event (worked)		24	24		24	27	24
City of Pewaukee 2012-2013	Ргесіріtяtіол Апоин (inches)	ę	0	0.5		0.5	2	0
	Pavement Temperature Pavement Temperature (F)							
	əgnası ərusaraquası AiA during event (^(T))	30	32	28		30	31	12
	to f Product Dsed (Tons)	70	40	54		45	50	30
	Product Used (bnrs\lfra=xim)	Salt	Salt	Salt	Salt	Salt	Salt	Salt
	(gal) bsed onivel flag	500	500	500	695	500	400	200
	γιητιγ	Plow	Plow	Salting Only	Pre-Wetting	Salting Only	Plow	Salting Only
	Date(s) of Event	6-Mar-13	6-Mar-13	12-Mar-13	15-Mar-13	16-Mar-13	18-Mar-13	19-Mar-13

Road Salt / Deicers Usage

0 #

9 Number of Entries

24 1272

> Total event hours worked

> > 3520

Total Salt Used (tons)

22679

Total Brine Used (gal)

Other Information

Page 60 of 93

P:\City\NR 216 Permit\Winter Management De-icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.Xisx

Road Salt / Deicers Usage	City of Pewaukee	2013-2014
---------------------------	------------------	-----------

Other Information	2" started at 6:30 am and ended at 11:00 am	2" started at 10:00 am	Snowed throughout the night: 3:00 am start		30 mph wind from the West	30 mph wind from the West	I" started at 3:00 am	25 mph wind from the Northwest	2" started at 2:00 am with another 2" during the day		0.5" started at 2:00 am	2" Clipper started @ 3:30 and ended at 7:30	0.5" from 5:00 am to 7:00 am	Rain with freezing rain	Freezing rain	Freezing rain	Freezing rain	9" started at 3:00 am	0.5" overnight	1" overnight	2" overnight	0.5" overnight	1" overnight	1" started at 3:00 pm	2" started at 7:00 am	2" started at 5:00 am	30 mph winds from Southwest and 1" of snow	Heavy freezing rain	Heavy freezing rain with 0.5" of ice	Roads refroze overnight	Still snowing back at 3:00 am	Total clean-up	Light dusting	I" all day snow	1" all day snow	1" all day snow	Light dusting	2" with a 40 mph wind and heavy drifting
Hours of Post-Event Clean-Up		0	0	27	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
242017 10 #/srovind 10 #	8	6	6		7	4	6	s	6	6	6	6	6	6	6	6	6	6	7	6	6	8	6	6	9	6	9	6	6	6	9	9	9	6	8	9	9	6
Hours of Event (worked)		38	45		28	12	27	15	36	40	27	27	27	20	32	27	18	66	18	27	32	36	27	24	32	27	27	27	27	27	27	42	25	30	24	25	27	38
Precipitation Amount (inches)	2	2	3	0	Drifting	Drifting	1	Drifting	2	2	0.5	2	0.5	Ice	Ice	Ice	Ice	9	0.5	1	2	0.5	1	-	2	2	1	Ice	Ice	Ice	3	0	0.5	-	1	1	0.5	2
Parement Temperature (T ^o) inoro guing event		21	16	25	7	7	6	17	25	28	17	18	20	31	22	28	28	31	24	4	19	19	8	13	21	22	30	34	35	32	24	14	25	15	19	15	18	12
9gnar Temperature Range during event (°F)	30	23	16	23	5	5	7	8	22	26	12	15	21	29	26	28	26	29	22	0	17	18	2	7	15	18	29	35	36	33	25	12	27	18	15	13	13	16
Amount of Product Used (Tons)	70	60	70	60	60	80	60	60	70	70	70	70	70	70	90	80	70	120	60	60	60	60	60	80	60	60	60	30	40	40	50	50	40	50	50	40	50	60
Product Used (bns2tlsz=xim)	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt
(lsg) bszU snirt Ils2	250	400	300	200	0	0	0	0	450	450	0	450	450	0	0	0	0	006	200	0	200	200	0	0	200	300	400	400	200	400	0	0	300	400	400	0	0	200
γίνἰτ	Salting Only	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow
Date(s) of Event	25-Nov-13	8-Dec-13	9-Dec-13	9-Dec-13	10-Dec-13	10-Dec-13	11-Dec-13	11-Dec-13	14-Dec-13	14-Dec-13	-Dec-13	G ^{6-Dec-13}	G 7-Dec-13	D ^{9-Dec-13}	O -Dec-13	→Dec-13	Q 1-Dec-13	2-Dec-13	6-Dec-13	2 4-Dec-13	25-Dec-13	26-Dec-13	31-Dec-13	31-Dec-13	1-Jan-14	2-Jan-14	4-Jan-14	10-Jan-14	10-Jan-14	11-Jan-14	14-Jan-14	15-Jan-14	16-Jan-14	17-Jan-14	18-Jan-14	20-Jan-14	22-Jan-14	25-Jan-14

P:\City\NR 216 Permit\Winter Management De-icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xisx

						_													-
	Other Information	3" started at 3:00 am	40 mpli wind out of the Northwest	1" from fast moving system	All day snow	2" overnight	1" from fast moving system	0.5" in 4 hours	2" from fast moving system	6" all day snow	freezing rain turning to snow	1" of rain with temps drapping	Light dusting of snow	2" overnight	2" overnight	3" from fast moving system	Light dusting of snow	1" overnight	
	Hours of Post-Event Clean-Up		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	54
	2.5 Drivers/# 10 #/2.10	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	Number of Entries
	Hours of Event (worked)		72	30	74	30	32	27	36	96	36	18	27	30	42	64	27	30	20.13
2013-2014	Precipitation Amount (inches)	3	Drifting	1	2	2	1	0.5	2	6	1	0	0.5	2	2	ŝ	0.5	1	Average Pavement Temp. per Entry (deg F)
	Pavement Temperature (T ^o) tnove guring event (^o F)	12	2	28	18	23	12	18	28	26	31	26	1	16	8	15	18	22	18.7
	sgnas Furgerature Range Air Temperature (T°F) during event (°F)	15	0	26	15	20	15	20	26	25	32	26	0	15	6	13	16	18	Average Air Temp per Entry (deg F)
	to the of Product Used (Tons)	60	50	50	60	50	40	50	40	70	30	30	40	40	50	50	50	40	<u>3160</u>
	Product Used (bnrs\track(m)	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Total Salt Used (tons)
	(lsg) bseU snir& Jls2	0	0	400	500	40	100	400	400	500	200	200	0	400	0	200	200	300	<u>11490</u>
	Αείτνῒις	Plow	Plow	Plow	Plow	Plow	Plow	Salting Only	Plow	Plow	Plow	Salting Only	Plow	Plow	Plow	Plow	Plow	Plow	Total Brine Used (gal)
	Date(s) of Event	26-Jan-14	27-Jan-14	30-Jan-14	1-Feb-14	5-Feb-14	8-Feb-14	12-Feb-14	13-Feb-14	17-Feb-14	20-Feb-14	JI-Feb-14	027-Feb-14	D 1-Mar-14	D _{2-Mar-14}	9 -Mar-14	5 -Mar-14	Q5-Mar-14	f 93

Road Salt / Deicers Usage City of Pewaukee Total event hours worked 1863

P:\City\NR 216 Permit\Winter Management De-icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xlsx

	Other Information	2" of snow: very icy	1 " overnight	1" of snow: 7:00 am run	Light iceing	3" total precip; rain changing to snow	2" overnight	Light iceing	1 " overnight; fast moving system	Light iceing	Light iceing	3" changing to freezing rain	2" of blowing snow	2" of blowing snow	3" of snow with high winds	1" during rush hour	2" overnight	Drifting and stush run	2" overnight	Light dusting of snow	1" overnight; fast moving system	Light iceing	Beginning of storm		9" total accumulation with high winds	2" from fast moving system	Light dusting of snow	1" from fast moving system	2" from fast moving system	
	Hours of Post-Event Clean-Up		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	22
	2 Drivers/# of Drivers	6	6	8	6	8	6	6	6	8	8	6	6	6	6	6	6	7	9	6	6	6	6	6	6	6	6	6	9	Number of Entries
	fiours of Event (worked)		27	24	22	36	45	18	36	22	24	36	96	45	27	30	30	21	24	21	24	18	40	40	54	30	30	20	36	20.89
2014-2015	Precipitation Amount (inches)		1	1	Ice	3	2	Ice	1	Ice	Ice	3	2	2	3	1	2	0	2	0.5	1	Ice			6	2	1	1	2	Average Pavement Temp. per Entry (deg F)
	Pavement Temperature (⁹ F) tervegent (⁹ F)		29	21	32	30	28	28	27	31	30	29	13	4	3	0	8	12	28	26	26	31	14	14	10	15	5	16	27	19.48
	Air Temperature Range during event (°F)	24	27	18	30	28	25	29	28	34	31	32	10	0	0	-2	6	8	27	27	24	34	10	10	8	13	3	12	30	Average Air Temp per Entry (deg F)
	dont of Product Used (Tons)	80	60	70	40	80	80	60	80	60	60	120	80	80	120	80	80	80	90	60	70	50	120	120	150	100	100	100	120	<u>2390</u>
-	dosU doued Used (bass/des=xim)		Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Total Salt Used (tons)
	Salt Brine Used (gal)	400	300	300	400	400	300	300	300	200	200	300	0	0	0	0	0	0	300	300	400	100	0	0	0	0	0	0	300	4800
	ζήνηςΑ	Plow	Salting Only	Salting Only	Salting Only	Plow	Plow	Salting Only	Plow	Salting Only	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Salting Only	Plow	Salting Only	Plow	Plow	Plow	Plow	Salting Only	Plow	Plow	Total Brine Used (gal)
	Date(s) of Event	15-Nov-14	16-Nov-14	19-Nov-14	22-Nov-14	24-Nov-14	25-Nov-14	28-Nov-14	2-Dec-14	8-Dec-14	18-Dec-14	Jan-15	e 4-Jan-15	G _{6-Jan-15}	B ^{8-Jan-15}	9 -Jan-15	2 .Jan-15	O ^{9-Jan-15}	21-Jan-15	65-Jan-15	2 6-Jan-15	29-Jan-15	1-Feb-15	1-Feb-15	2-Feb-15	3-Feb-15	18-Feb-15	25-Feb-15	3-Mar-15	

Road Salt / Deicers Usage City of Pewaukee 903

Total Event hours worked

P:\City\NR 216 Permit\Winter Management De-icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xisx

of Pewaukee
City

	Other Information			Very Heatw.				High wind followed by a slush run and a lot of driftinge			Rain froze over night.	Rain /słush mix.	One inch with areas of 4 inches.	One inch overnight with high winds.	One inch overnight.	One inch - very dry.	One inch overnight.	One inch overnight. Three inches during the day.	Two inches overnight.	Light icing to 3 inches of wet snow.	Two inches fast mover				
	Jours of Post-Event Dean-Up																								<u>67</u>
	24 Of Drivers/# of Trucks	4	6	6	8	6	6	6	6	8	8	8	8	6	6	6	6	6	6	8	6				Number of Entries
99	Hours of Event worked)			100	32	27	36	75	24	24	24	24	26	36	36	27	36	06	27	76	32				<u>26.89</u>
City of rewaukee 2015-2016	Precipitation Amount (inches)			10	1	2	1	2	1	0.5	Ice	slush	1+4	1	-	1	1	4	2	Ice/3 inches	2				Average Pavement Temp. per Entry (deg F)
	Pavement Temperature Range during event (°F)	32	30	35	32	28	13	6	33	32	24	31	28	16	15	18	18	28	31	31	30				<u>27.26</u>
	əgnası ərutarəqməT tik Air Temperaturə (T°) trayış gairub		30	35	32	29	13	4	32	31	26	35	30	14	12	22	21	28	32	31	29				Average Air Temp per Entry (deg F)
	Amonnt of Product Used (Tons)	110	150	90	60	80	100	175	75	75	75	75	80	80	80	80	100	160	60	200	50				<u>1955</u>
	DosU toubord (bnrs\lfra=xim)	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt				Total Salt Used (tons)
	Salt Brine Used (gal)	500	500	0	200	350	0	0	350	200	200	300	300	0	0	0	300	800	300	500	300				<u>0075</u>
	λείτντές	Plow	Plow	Plow	Salt	Plow	Plow	Plow	Plow	Plow	Salt	Salt	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow/Salt	Plow				Total Brine Used (gal)
	Date(s) of Event	21-Nov-15	21-Dec-15	22-Dec-15	7-Jan-16	9-Jan-16	10-Jan-16	12-Jan-16	25-Jan-16	26-Jan-16	1-Feb-16	D-Feb-16	O 8-Feb-16	G ^{9-Feb-16}	U10-Feb-16	9 4-Feb-16	Feb-16	Ol-Mar-16	3-Mar-16	64-Mar-16	2 -Apr-16				

Total Event Hours Worked 812

	Other Information	Lone storm start 8-00am and end 8-00am. Clean an included	Pre-storm treatments	Start 7-00m on the 10th	End 8nm on the 11th	30mph winds - drift run.	run.	Light dusting followed by long duration storm starting at 2:00pm.	Still snowing.	Storm ends.			Fast moving storm.	Light icing.	Pre-storm salting.	I inch snowfall overnight followed by freezing rain.	Freezing rain.	Freezing rain.	Ereezing rain.	Ereezing rain.	Light snow.	1 inch overnight.	Pre-storm treatments followed by a salt run.	2 inches overnight.		Light freezing rain.	Light freezing rain.	1 inch overnight.	1 inch in morning followed by light snow all day.	Start storm with 3 inches and continues to snow.	Storm wraps up with 6 inch total.		Light freezing rain.	
	Javrs of Post-Event Clean-Up)	Pre-	Star	End	30m	Drift run	Ligh	Still	Ston	50	50	Fast	Ligh	Pre-	I inc	Free	Free	Free	Free	Ligh	I inc	Pre-	2 inc		Ligh	Ligh	I inc	I inc	Star	Stor		Ligh	29
	8 of Drivers/# of Trucks	6		10	10	6	4	8 to 10	10 to 9	6	6	6	6	8	6	6	6	6	6	5	6	6	6	6		8	9 to 8	6	6	6	6		8	Number of Entries
66	Hours of Event worked)			50	55	16	16	64	88	50	36	36	50	32	24	84	27	76	27	15	36	36	18	36		22	36	30	47	81	32		24	<u>28.23</u> Ni
City of rewaukee 2016-2017	Precipitation Amount (inomA noitation)			4	5	0	0	7	6	2	0	0	4	ice	1	1	ice	ice	ice	ice	0.5	1	1	2		ice	ice	1	2		6		ice	Average Pavement Temp. per Entry (deg F)
	Pavement Temperature (T°) fange during event	29		22	27	6	10	11	18	9	14	30	30	34	31	31	26	32	32	32	32	29	29	29		32	31	25	28	25	19		31	4 7 7 8 7 8
	9gnas Turterature Range Air Temperature (1°)	31		24	28	6	8	10	16	8	12	26	31	34	34	34	28	34	34	32	32	27	27	29		31	30	23	32	22	18		32	Average Air Temp per Entry (deg F)
	tonbrd of Product Used (Tons)		0	80	80	60	80	140	170	80	60	60	80	90	60	260	120	260	80	40	60	80	70	80	0	60	140	100	120	130	50		50	<u>2900</u>
	Product Used (bna2dla2=xim)	Salt		Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt		Salt	Salt	Salt	Salt	Salt	Salt		Salt	Total Salt Used (tons)
	(lsg) Dsed (gal)	850	750	400	300	0	0	0	0	0	0	100	300	100	200	400	400	006	300	100	300	300	1400	300	1390	300	400	200	400	400	200	335	200	11225
	γείλιμλ	Plow	Pre-storm	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Salt	Salt	Plow/salt	Salt	Salt	Salt	Salt	Salt	Plow	Plow	Plow	Pre-storm	Salt	Salt	Plow	Plow	Plow	Plow	Pre-storm	Salt	Total Brine Used (gal)
	Date(s) of Event	4-Dec-16	9-Dec-16	10-Dec-16	11-Dec-16	14-Dec-16	15-Dec-16	16-Dec-16	17-Dec-16	18-Dec-16	19-Dec-16	2)-Dec-16	Q ^{3-Dec-16}	B 3-Jan-17	D ^{9-Jan-17}	9 0-Jan-17	6 ^{1-Jan-17}	O ^{16-Jan-17}	-Jan-17	6 ^{8-Jan-17}	2 5-Jan-17	26-Jan-17	30-Jan-17	31-Jan-17	3-Feb-17	12-Feb-17	24-Feb-17	25-Feb-17	1-Mar-17	13-Mar-17	14-Mar-17	16-Mar-17	17-Mar-17	

Road Salt / Deicers Usage City of Pewaukee

P:\City\NR 216 Permit\Winter Management De-Icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xisx

Total Event Hours Worked 1171

	Other Information	All night snow	Fast moving storm - 1 inch	Light Dusting	2" north part of City/dusting south part of City	Flurries predicted - 1.5 inches	Light Dusting	Fast moving storm -2 inches	East moving storm -1 inch	Fast moving storm - 1 inch	Fast moving storm -1 inch	I inch overnight.	I inch overnight.	Rain to ice	3 inches overnight - slow mover	3 inches - same storm lake effect	Slush run	Heavy rain changing to snow turning to hardpack	Fast moving storm - 1 inch	I inch beginning of storm	7 inches of snow - total storm was 8 inches	I inch - still snowing	1 inch overnight.	4 inches - 12 hour storm	Light Dusting	Fast moving storm - 3 inches	Rain changing to snow	Hard pack ice	Light icing	Rain with heavy snow	1 inch - slow mover	2 inches - still snowing	5 inches total from storm -wet and heavy	
	Hours of Post-Event Clean-Up																24																	<u>32</u>
	# of Drivers## of Trucks	6	6	6	6	6	6	6	6	6	8	8	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	Number of Entries
	Hours of Event (worked)	64	27	24	24	27	24	36	27	22	22	24	27	36	56	36	24	72	20	27	108	27	36	72	18	36	36	0	20	108	36	63	36	<u>23.06</u>
2017-2018	Precipitation Amount (inches)	2	1	0.5	2	1.5	0.5	2	1	1	1	1	1	ice	3	3	0	4	1	1	7	1	-	4	0.5	3	2	0	ice	4	1	2	3	Average Pavement Temp. per Entry (deg F)
	erutaraqmət Temperature (T°) tnəvə guring event		22	19	30	26	25	22	18	14	15	10	15	32	24	22	28	28	28	29	18	8	6	16	28	31	22	26	28	30	28	32		23.34
	sgnes Range Air Temperature Range during event (°F)	26	26	22	32	28	28	22	16	14	15	8	15	34	28	24	24	28	28	29	16	8	6	14	28	31	21	24	28	30	28	32	34	Average Air Temp per Entry (deg F)
	Amount of Product Used (Tons)	100	80	60	50	50	50	80	60	80	80	80	80	80	120	80	50	160	60	160	240	120	120	180	100	100	100	100	100	250	180	140	75	<u>3365</u>
	Product Used Product Used (bnrs\three	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Total Salt Used (tons)
	Salt Brine Used (gal)	500	300	300	300	500	100	350	200	0	0	0	0	0	300	200	200	400	400	400	400	0	0	0	400	400	0	0	0	0	0	0	0	<u>5650</u>
	үйлэА	Plow	Salt	Salt	Salt	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Salt	Plow	Plow	Plow	Plow	Salt	Plow	Plow	Plow	Plow	Plow	Salt	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Total Brine Used (gal)
	Date(s) of Event	9-Dec-17	11-Dec-17	13-Dec-17	13-Dec-17	13-Dec-17	14-Dec-17	24-Dec-17	25-Dec-17	28-Dec-17	29-Dec-17	Dec-17	S ^{3-Jan-18}	B 1-Jan-18	O 15-Jan-18	9 -Jan-18	9 6-Jan-18	O ^{23-Jan-18}	28-Jan-18	6 -Feb-17	2 ^{4-Feb-18}	5-Feb-18	6-Feb-18	9-Feb-18	17-Feb-18	4-Mar-18	4-Apr-18	4-Apr-18	14-Apr-18	15-Apr-18	16-Apr-18	18-Apr-18	19-Apr-18	

Road Salt / Deicers Usage City of Pewaukee

P:\City\NR 216 Permit\Winter Management De-Icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xisx

1215

Total Event Hours Worked

sage	
S U	ling
icer	116/0
De	Do.
Salt /	tv of
Road	C

2018-2019

Other Information	Light Dusting	2 inches - fast mover	Lieht Dustine	Slower moving storm - lingering snow showers	Blizzard to the south - worked 3 routes south of L-94	1 inch overnight - slow mover	Light icing	Lieht Dustine	1 inch - fast mover	Light Dusting	Jce - very slippery	All day - changed to snow	Melt off and re-freeze	Light Dusting	Pre-wet run	Beginning of storm - 6 inches expected	Snow all night - total clean up	Beginning of storm - 5 inches expected	Total snow 7 inches	Light Dusting	Started at 3 am and snowed all day	Pre-wet/pre-salt runs - ice expected	1 inch of steet then rain then freezing	Freezing rain	Heavy rain turned to ice	Fast moving storm	Wet - heavy snow	1 inch overnight followed by lots of drifting	6 inclues of expected snow	End of storm - 7 inches	I inch snow with freezing rain	
Jours of Post-Event Clean-Up		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
2 of Drivers/# of Trucks	€ ₩	6	5	S	ę	6	8	~	6	6	6	6	6	6	1	6	6	6	6	6	6	6	10	10	10	10	10	10	10	10	10	
dours of Event worked)		27	27	24	12	32	24	24	30	22	27	45	32	27	8	30	80	27	96	22	180	21	140	60	30	24	110	50	32	40	60	
Precipitation Amount (inches)		2	-	1.5	0.05	-	Ice	0.05		0.05	0	2	Ice	0.05		1	5	1	6	0.05	п		1	Ice	Ice	1	6	1	2	2	1	
Pavement Temperature Range during event (°F)		32	30	30	30	29	32	31	30	32	32	30	31	32		21	21	21	21	4	21	26	30	32	31	28	30	22	26	24	28	
92nersture Range Air Tempersture Range during event (°F)		31	29	28	30	30	31	33	28	32	32	30	32	32		22	22	21	22	4	19	27	31	33	25	29	31	24	28	26	31	
to inuont of Product Used (Tons)	40	60	40	50	15	70	70	70	80	80	80	80	70	80	0	100	160	80	240	80	400	0	240	180	80	60	100	80	100	100	140	0
Product Used (bas2Use=xim)	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Brine	Salt	Salt	Salt	Salt	Salt	Salt	Brine	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Brine
(lsg) bszU snirt Ils2	200	200	200	300	200	200	300	200	100	200	200	200	200	150	700	200	0	200	200	0	0	500	400	500	200	300	400	200	200	200	300	820
ζήνης	Salt	Plow	Plow	Salt	Salt	Plow	Salt	Plow	Plow	Salt	Salt	Plow	Salt	Salt	Pre-wet	Plow	Plow	Plow	Plow	Salt	Plow	Pre-wet	Plow	Plow	Salt	Plow	Plow	Plow	Plow	Plow	Plow	Pre-wet
Date(s) of Event	9-Nov-18	10-Nov-18	16-Nov-18	17-Nov-18	26-Nov-18	29-Nov-18	2-Dec-18	12-Dec-18	25-Dec-18	28-Dec-18	Z-Dec-18	G1-Dec-18	B _{2-Jan-19}	D _{2-Jan-19}	9 -Jan-19	2 8-Jan-19	O ^{19-Jan-19}	22-Jan-19	6:-Jan-19	2 6-Jan-19	28-Jan-19	5-Feb-19	6-Feb-19	7-Feb-19	7-Feb-19	10-Feb-19	12-Feb-19	13-Feb-19	17-Feb-19	18-Feb-19	20-Feb-19	22-Feb-19

	Other Information	Ice with rain to follow	Heavy rain over night that turned to ice with 60 mph wind	r night	2 inches from fast moving over night storm	ing				
		Ice with ra	Heavy rain	I inch over night	2 inches fr	Light Dusting				
	Hours of Post-Event Clean-Up		0	0	0	0	0		<u>30</u>	
	2, Drivers/# of Drivers	10	10	10	6	10	10		Number of Entries	
s Usage kee	Hours of Event (worked)		24	40	30	25	30		<u>28.76</u>	
Road Salt / Deicers Usage City of Pewaukee 2018-2019	Precipitation Amount (inches)	Ice	Ice	1	2	0.05	1		Average Pavement Temp. per Entry (deg F)	1564
Ro	Pavement Temperature Range during event (°F)	31	29	24	11	4	31		29.18	Total Event Hours Worked
	əgnsA ərufərəqnəf AiA Air Temperature Range (T°)	32	31	25	13	6	32		Average Air Temp per Entry (deg F)	
	toning of Product Dsed (Tons)	80	80	80	80	10	10		<u>3365</u>	
	Product Used Product Used (DnesVles=xim)	Salt	Salt	Salt	Salt	Salt	Salt		Total Salt Used (tons)	
	Salt Brine Used (gal)	400	100	100	0	0	300		<u>9070</u>	Brine 0 1200 1200 1650 4620 300
	Αείλνίζγ	Salt	Salt	Plow	Plow	Plow	Plow		Total Brine Used (gal)	Salt 5alt 0 275 460 1210 1320 100
	Date(s) of Event	23-Feb-19	24-Feb-19	27-Feb-19	2-Mar-19	5-Mar-19	10-Mar-19		Pa	de go becember ^{January} ^{March}

	9 Doctober	vember	cember	пиагу	bruary	Aarch		
age	Ő	8	Dec		Fet	ğ	3	

P:\City\NR 216 Permit\Winter Management De-Icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xisx

Road Salt / Deicers Usage	City of Pewaukee	2019-2020
---------------------------	------------------	-----------

	Т		Т	Т	Τ	Т	Т	Т		Г		Г		Т	1				Γ			-							_	1
Other Information	Happy Halloween Slow mover: 2- RUNS	2" Started @ 34M done @ 94M	1" continuation of storm	2 "Very slippery: 2- Runs	1" fast mover	······································	Light mist turned to Ice	l" overnight	5" overnight super slippery: 2- Runs	Pre-Salt prior to Storm10" incluse expected	ICE Temperature Dropped 6 Degrees in 30 Minutes	Beginning of Strom	End of Strom	2" overnight	Pre salt Run	Beginning of Storm	6" Total from storm High Winds coming; 2- Runs	Overnight Beginning of long drawn out storm	Storm continuing	Still Snowing	Still Stowing	End of Storm8" Total	Start of storm 5" perdicted.	Total storm 8" Fast mover	Quick mover Cold Blast to follow: 2- Runs	Beginning of storm	Fast mover 4 " total			
Javr: of Post-Event Clean-Up																														26
8 of Drivers/# of Trucks	∉ ∞	8	8	6	7		6	6	10	6	10	10	10	10	6	10	10	10	10	10	10	10	10	10	10	10	10			Number of Entries
Hours of Event worked)		32	24	96	24		30	27	80	27	30	30	50	30	27	30	80	40	40	40	50	50	30	50	120	40	40			<u>29.4</u>
Precipitation Amount (inchesi)		2	-	m	1		Ice	1	4	0	ICE	1.	3"	2"	0	3	3	2	1	2	1	2	2	5	4	6	2			Average Pavement Temp. per Entry (deg F)
Pavement Temperature Pavenge during event (°F)		28	27	23	27		29	23	24	34	27	27	25	30	31	31	31	31	33	32	32	32	31	28	10	30	30			<u>30.56</u>
9gnas Rauterature Range (P) Tangerature (P)	28	30	30	22	28		31	21	26	32	28	26	24	32	32	32	32	32	34	36	34	36	32	30	12	32	32			Average Air Temp per Entry (deg F)
Mount of Product Used (Tons)		70	70	160	60		80	80	150	50	100	80	120	80	50	80	140	80	100	80	80	60	100	100	180	80	80			<u>2450</u>
basU toubor¶ (bnss\/ls2=xim)		Salt	Salt	Salt	Salt		Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt			Total Salt Used (tons)
(leg) bozU onirA tla2	300	300	300	400	300	850	500	300	300	0	0	300	300	300	0	300	300	300	300	300	300	300	300	300	0	300	300			<u> 7750</u>
ζινηλ	Plow	Plow	Plow	Plow	Plow	Pre-wet	Salt	Plow	Plow	Salt	Salt	Salt	Salt	Salt	Salt	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow	Plow			Total Brine Used (gal)
Date(s) of Event	31-Oct-19	6-Nov-19	6-Nov-19	11-Nov-19	14-Nov-19	12-Dec-19	14-Dec-19	16-Dec-19	31-Dec-19	10-Jan-20	11-Jan-20	B ^{1-Jan-20}	G _{1-Jan-20}	$\mathbf{\theta}_{^{13-Jan-20}}$	9 V-Jan-20	6 _{7-Jan-20}	O 18-Jan-20	23-Jan-20	6 ^{4-Jan-20}	2 4-Jan-20	25-Jan-20	25-Jan-20	9-Feb-20	9-Feb-20	13-Feb-20	17-Feb-20	18-Feb-20			

Total Event Hours Worked 1213

P:\City\NR 216 Permit\Winter Management De-icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xlsx

		Other Information							
		torrad of Post-Event Jurns of Post-Event							
		2 Of Drivers/# of Trucks	ŧ						
rs Usage	ıkee	Hours of Event (worked)							
Road Salt / Deicers Usage	City of Pewaukee 2019-2020	Precipitation Amount (inches)							
Ro		Рачетен Тетрегатиге Рачетен Тетрегатиге Капде during event (°F)							
		əgnası əruserəture Range during event (°F)							
		Amount of Product Used (Tons)							
		Product Used (bns2/lfs2=xim)							
		Salt Brine Used (gal)	Brine	140	1300	1950	3000	1200	0
		ζίττις	Salt	300	360	310	1100	540	0
		Date(s) of Event		October	November	December	January	February	March

	Other Information	Heavey snow all day long; 2 runs	Light snow but very icy	Pre-wet application prior to event	Heavy wet snow, fast mover; 2 runs	1 inch of snow predicted, received 4 inches; 2 runs	Overnight storm, fast mover	Overnight storm, fast mover	Snowfall not originally forcasted, still received 1 inch	Pre-wet application prior to event	Light and fluffy snow	2 inches of snow predicted, received 8 inches with high winds; 3 runs	Pre-wet application prior to event	8 inches of heavy wet snow; 2 runs	Light dusting overnight	Temperatures falling with high winds; 2 runs	Packed snowlice with high winds, lots of drifting; 3 runs	2 inches of snow overnight; 2 runs	3 inches of snow and cold temperatures; 2 runs	2 inches of snow overnight; 2 runs	4 inches of snow overnight, fast mover; 2 runs					
	Hours of Post-Event Clean-Up																									<u>.</u> 26
	8 of Drivers/# of Trucks	10	10		10	п	10	10	10		10	10		10	7	10	10	10	10	10	10					Number of Entries
ee	Hours of Event (worked)		32		06	100	36	36	30		70	120		100	14	80	120	80	100	64	72					<u>16.83</u>
City 01 Pewaukee 2020-2021	Precipitation Amount (inches)		1		7	4	2	1	1		3	8		8	trace	3	2	2	3	2	4					Average Pavement Temp. per Entry (deg F)
	Pavement Temperature Pange during event (°F)		30		31	30	32	31	25		26	25		26	18	26	11	10	4	5	26					17.43
	əgnası və ture Range during event (°F)	32	31		33	32	34	32	26		24	26		28	20	32	10	6	0	4	31					Average Air Temp per Entry (deg F)
	toubort of Product Used (Tons)		100		160	160	100	100	100		150	210		180	40	120	100	150	150	160	80					2240
	Product Used (bna2/lfa2=xim)		Salt		Salt	Salt	Salt	Salt	Salt		Salt	Salt		Salt	Salt	Salt	Salt	Salt	Salt	Salt	Salt					Total Salt Used (tons)
	Salt Brine Used (gal)	600	400	768	500	400	300	300	300	951	500	800	600	600	200	300	0	0	0	0	300					<u> 7819</u>
	үіліэА	Plow	Plow	Pre-wet	Plow	Plow	Plow	Plow	Plow	Pre-wet	Plow	Plow	Pre-wet	Plow	Salt	Plow	Plow	Plow	Plow	Plow	Plow					Total Brine Used (gal)
	Date(s) of Event	12-Dec-20	27-Dec-20	29-Dec-20	30-Dec-20	1-Jan-21	15-Jan-21	16-Jan-21	19-Jan-21	13-Jan-21	24-Jan-21	25-Jan-21	2 -Jan-21	O 1-Jan-21	G -Feb-21	A ^{1-Feb-21}	Feb-21	R-Feb-21	D ^{3-Feb-21}	J -Feb-21	G-Feb-21	3				

Road Salt / Deicers Usage City of Pewaukee

P:\City\NR 216 Permit\Winter Management De-icing Program\Master Winter Road Management_deicing event form_Dec 2010 to present.xisx

Total Event Hours Worked 1230

	Other Information							
	Hours of Post-Event Clean-Up							
	z401 Drivers/# 0f Trucks							
rs Usage ukee I	Hours of Event (worked)							
Road Salt / Deicers Usage City of Pewaukee 2020-2021	Precipitation Amount (inches)							
Ro	Pavement Temperature Pavement Temperature Range during event (°F)							
	agnes ture Range Air Temperature Range during event (°F)							
	Amount of Product Used (Tons)							
	DseU 1500 Product Used (baasUlas=xim)							
	(gal) Brine Used (gal)	Salt	0	0	440	1000	800	0
	γίνης	Brine	o	o	2268	4751	800	O
	Date(s) of Event		October	November	December	January	February	March

Page 72 of 93

Item D

Fiscal Analysis Worksheets

Spreadsheet for Fiscal Analysis Portion of City of Pewaukee's 2020 MS4 Annual Report

	Budget for Reporting Year	Annual Expenditures for Reporting year	Budget for Upcoming Year
Public Education and Outreach	\$1,500.00	\$1,465.50	\$1,500.00
Public Involvement and Participation	\$1,500.00	\$1,465.50	\$1,500.00
Illicit Discharge Detection and Ellimination	\$1,370.00	\$2,610.00	\$1,430.00
Construction Site Pollution Control	\$25,161.00	\$75,790.00	\$36,575.00
Post-Construction Storm Water Management	\$33,161.00	\$30,290.00	\$44,575.00
Pollution Prevention	\$729,226.00	\$639,760.56	\$824,101.10
Storm Water Quality Management	\$350,000.00	\$0.00	\$350,000.00
Storm Sewer System Map	\$5,000.00	\$6,999.90	\$5,000.00
Totals	\$1,146,918.00	\$758,381.46	\$1,264,681.10

Page 74 of 93

Public Information and Outreach

\$1,500.00	ar \$1,465.50	\$1,500.00
Budget for Reporting Year	Expenditures for Reporting Year	Budget for Upcoming year

contracted amount to Waukesha County. This dollar figure is half of the reported/budgeted number as the Public Budget item for reporting purposes is identified as Permit Compliance-Information and Education and includes Involvement and Participation program is included in here as well. Note: for upcoming year budget, dollars are estimated for reporting purposes and may not necessarily correspond to the City's Budget summary. DNR catagories do not correspond to City Budget Accounting Fields.

Public Involvement and Participation

\$1,500.00	ar \$1,465.50	\$1,500.00
Budget for Reporting Year	Expenditures for Reporting Year	Budget for Upcoming year

contracted amount to Waukesha County. This dollar figure is half of the reported/budgeted number as the Public Budget item for reporting purposes is identified as Permit Compliance-Information and Education and includes Education and Outreach program is included in here as well. Note: for upcoming year budget, dollars are estimated for reporting purposes and may not necessarily correspond to the City's Budget summary. DNR catagories do not correspond to City Budget Accounting Fields.

Illicit Discharge Detection and Ellimination Program

identified MS4 outfalls and review reports. Costs will include estimates of time spent persuing spills/dumping complaints by Budget item for reporting purposes is an estimation of Engineering Tecnicians time and Civil Engineers time to inspect Engineering Staff and by City Fire Services. Note: for upcoming year budget, dollars are estimated for reporting purposes and may not necessarily correspond to the City's Budget summary. DNR catagories do not correspond to City Budget Accounting Fields. Fire Dept. projections are not included for budget purposes as Fire is a 24/7 service and is a required service regardless of whether or not a spill occurs.

Budget for Reporting Year

Hours Cost	20.00 \$751.80 4.00 \$164.72 6.00 \$246.60 2.00 \$112.64 1.00 \$67.34 \$27.34 \$17.309.85 Subtotal	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00	0.00 Subtotal
Engineering Staff Hourly Wage	Engineering Technician\$37.59Senior Engineering Technician\$41.18Civil Engineer\$41.10Chief Engineer-Utilities\$56.32DPW Director\$67.34Mileage costs\$67.34Fire Department Staff	Fire Paid on Premise Division Chief \$35.00	Fire Paid on Premise Driver/Paramedic \$25.56	Fire Paid on Premise Fire Fighter \$17.04	Paramedic \$21.30	Engine Cost \$650.00	Ambulance \$500.00	Command Vehicle \$62.00	

\$1,424.43 Subtotal

\$27.

\$119.24 \$77.34

4.00 6.00 2.00 1.00

\$42.42 \$42.12 \$59.62 \$77.34

\$169.68 \$252.72 0C 8178

20.00

\$38.91

Cost

Hours

Hourly Wage

Budget Upcoming Year

Annual Expenditures for Rporting Year

\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00

\$35.00 \$28.40 \$17.75

0.00 0.00 0.00 0.00 0.00 0.00

\$24.14 \$650.00 \$500.00 \$62.00

\$0.00 Subtotal

\$0.00

\$1,424.43 Total \$1,430.00 Use

> Engine cost assumed based on apparatus cost of 650,000 with 10 year life cycle and 100 hours of use per year. Command Vehicle assumed based on cost of 49,613 with 8 year life cycle and 100 hours of use per year.

ALS Unit assumed based on cost of 350,000 with 7 year life cyle and 100 hours of use per year.

Mileage costs based on vehicle distance of 30 miles (expenditures) and 50 miles (budget) at mileage rate of 53.5 cents for 2017 and 54.5 cents for 2018. Wages based upon hourly rate multiplied by 1.42 to account for benefits, etc.

Page 77 of 93

Construction Site Pollutant Control Program

Note: The City's Construction Site Pollution Control Program includes compliance inspections, enforcement, erosion control plan review and permitting. The financial estimates contained in this spreadsheet are for construction sites over an acre only and do not include estimates of Building Inspection costs. Developer driven expenditures are generally billed back to the Developer. Budget dollars are taken from line items under "Permit Compliance" in the Storm Water Utility Budget (one half of Numbers 230-53656-51290 and 230-53656-51950 and all of 230-53656-53530).

Budget for Reportin	ng Year	\$25,161.00		Budget for	· Upcoming Y	lear		\$36,575.00
Annual Expenditur	es for Reporting Year	\$75,790.00						
Project	Briohn Bldrs-Angulu	s Bldg Springdale Rd R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	Wages \$37.59 \$41.18 \$41.10 \$56.32 \$67.34	0.00 0.00 0.00 10.25	Total \$6,033.01 \$0.00 \$0.00 \$0.00 \$577.28 \$0.00	Total	\$6,610.29	9
	Rainbow Childcare	R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	0.00 3.75 20.25	\$7,513.08 \$0.00 \$0.00 \$154.13 \$1,140.48 \$0.00	Total	\$8,807.69	9
	Briohn Builders Nort	hmound Bldg R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	0.50 0.00	\$5,745.62 \$0.00 \$20.59 \$0.00 \$619.52 \$0.00	Гotal	\$6,385.72	8
	Christ Evangelical Lut	herine Church R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	0.00 0.00 0.00 13.50 0.00	\$5,974.79 \$0.00 \$0.00 \$0.00 \$760.32 \$0.00 7	Γotal	\$6,735.11	1
	Swan View Farms Ph.	1 R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech	\$37.59 \$41.18	0.00 0.00	\$9,100.24 \$4,001.20 \$0.00 \$0.00			

Page 78 of 93

	Civil Engineer Chief Engineer-Utilities DPW Director	\$41.10 \$56.32 \$67.34	0.00 \$0.00 56.00 \$3,153.92 0.00 \$0.00 Total	\$16,255.36
Swan View Farms Pl	n. 2 R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$0.00 \$1,314.73 0.00 \$0.00 0.00 \$0.00 0.00 \$0.00 1.75 \$98.56 0.00 \$0.00 Total	\$1,413.29
Woodleaf Reserve P	hase 3 R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$2,778.43 \$0.00 0.00 \$0.00 0.00 \$0.00 0.00 \$0.00 5.50 \$309.76 0.00 \$0.00 Total	\$3,088.19
Glen of Parkway Rid	ge R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$4,231.95 \$598.29 0.00 \$0.00 0.00 \$0.00 2.00 \$82.20 18.00 \$1,013.76 0.00 \$0.00 Total	\$5,926.20
James Craig Builders	-Swan Road R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$0.00 \$0.00 0.00 \$20.59 0.00 \$0.00 1.25 \$70.40 0.00 \$0.00 Total	\$90.99
Baenen_Northview F	Road R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$0.00 \$0.00 0.00 \$0.00 0.00 \$0.00 7.75 \$436.48 0.50 \$33.67 Total	\$470.15
Klein Dickert Glass	R/M Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$7,475.15 \$0.00 0.00 0.00 0.00 \$0.00 16.00 \$901.12 0.00 \$0.00	

Page 79 of 93

Page 80 of 93

	R/M Bills			\$0.00	
	AECOM Bills				
	Engineer Tech	\$37.59	0.00	\$0.00	
	Sr. Engineer Tech	\$41.18	0.00	\$0.00	
	Civil Engineer	\$41.10	0.00	\$0.00	
	Chief Engineer-Utilities	\$56.32	2.25	\$126.72	
	DPW Director	\$67.34	2.00	\$134.68	
				Total	\$261.40
	R/M Bills			\$0.00	
	AECOM Bills				
	Engineer Tech	\$37.59	0.00	\$0.00	
	Sr. Engineer Tech	\$41.18	0.00	\$0.00	
	Civil Engineer	\$41.10	0.00	\$0.00	
	Chief Engineer-Utilities	\$56.32	0.00	\$0.00	
	DPW Director	\$67.34	0.00	\$0.00	
				Total	\$0.00
	R/M Bills			\$0.00	
	AECOM Bills	Contraction Plantal			
	Engineer Tech	\$37.59	0.00	\$0.00	
	Sr. Engineer Tech	\$41.18	0.00	\$0.00	
	Civil Engineer	\$41.10	0.00	\$0.00	
	Chief Engineer-Utilities	\$56.32	0.00	\$0.00	
	DPW Director	\$67.34	0.00	\$0.00 Total	£0.00
				Total	\$0.00
	R/M Bills			\$0.00	
	AECOM Bills			\$0.00	
	Engineer Tech	\$37.59	0.00	\$0.00	
	Sr. Engineer Tech	\$41.18	0.00	\$0.00	
	Civil Engineer	\$41.10	0.00	\$0.00	
	Chief Engineer-Utilities	\$56.32	0.00	\$0.00	
	DPW Director	\$67.34	0.00	\$0.00	
				Total	\$0.00
展示"新闻 "					
	R/M Bills			\$0.00	
	AECOM Bills				
	Engineer Tech	\$37.59	0.00	\$0.00	
	Sr. Engineer Tech	\$41.18	0.00	\$0.00	
	Civil Engineer	\$41.10	0.00	\$0.00	
	Chief Engineer-Utilities	\$56.32	0.00	\$0.00	
	DPW Director	\$67.34	0.00	\$0.00	
00000000000000000000000000000000000000				Total	\$0.00
	R/M Bills			\$0.00	
	AECOM Bills	000000	0.00		
	Engineer Tech	\$37.59	0.00	\$0.00	
	Sr. Engineer Tech	\$41.18	0.00	\$0.00	
	Civil Engineer	\$41.10	0.00	\$0.00	
	Chief Engineer-Utilities	\$56.32	0.00	\$0.00	
	DPW Director	\$67.34	0.00	\$0.00 Total	0.00
				Total	\$0.00

Post Construction Storm Water Management

Note: The City's Post Construction Site Storm Water Management Program Program includes pond inspections, review of maintenance agreements, plan review and permitting. Estimates are provided for Engineer Tech's review of Wagner Park Ponds and Civil Engineer's review of the Green Road Pond, the Pewaukee Sports Complex Ponds, City Hall Bio-infiltration device and the Rockwood Drive Pond. Developer driven expenditures are generally billed back to the Developer. Budget dollars are taken from line items under "Permit Compliance" in the Storm Water Utility Budget (one half of Numbers 230-53656-51290 and 230-53656-51950 and all of numbers 230-53656-52150 and 230-53656-53510).

Budget for Reportin	ng Year	\$33,161.00		Budget for Upcomi	ng Year		\$44,575.00
Annual Expenditure	es for Reporting Year	\$30,290.00					
Project	Green Acres LLC Offic	e Building AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	Wages \$37.59 \$41.18 \$41.10 \$56.32 \$67.34	0.00 \$0 0.00 \$0 4.50 \$253	.00 .00 .00	\$1,331.94	
	Pewaukee Industrial S	outh AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$2,886 0.00 \$0 0.00 \$0 1.00 \$41 3.50 \$197 0.00 \$0	.00 .00 .10 .12	\$3,124.81	I
	Glen at Parkway Ridge	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$1,794. 0.00 \$0. 0.00 \$0. 2.25 \$92. 14.00 \$788. 0.00 \$0.	00 00 48 48	\$2,675.83	l
	Swan View Farms Ph 2	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$12,003. 0.00 \$0. 0.00 \$0. 0.00 \$0. 56.25 \$3,168. 0.00 \$0.	00 00 00 00	\$15,171.59	I.
	Swan View Farms Ph 2	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities	\$37.59 \$41.18 \$41.10 \$56.32	\$1,314. 0.00 \$0. 0.00 \$0. 2.25 \$92. 0.00 \$0.	00 00 48		

Page 82 of 93

	DPW Director	\$67.34	0.00 <mark>\$0.0</mark>	<mark>0</mark> Total	\$1,407.22
Klein Dickert Glass					
	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$1,143.2 0.00 \$0.0 0.00 \$0.0 0.00 \$0.0 7.75 \$436.4 0.00 \$0.0	0 0 8	\$1,579.72
Green Road Pond Ins	pection				
	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$0.00 0.00 \$0.00 1.50 \$61.6: 0.00 \$0.00 0.00 \$0.00 0.00 \$0.00) 2	\$61.65
Christ Evangelical Chu	ırch				
	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$0.00 0.00 \$0.00 0.00 \$0.00 0.00 \$0.00 2.75 \$154.88 0.00 \$0.00)) }	\$154.88
Waters Senior Living					
	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$2,914.72 0.00 \$0.00 0.00 \$0.00 3.25 \$133.58 6.25 \$352.00 0.00 \$0.00)))	\$3,400.30
Rainbow Childcare					
	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$0.00 0.00 \$0.00 0.00 \$0.00 3.75 \$154.13 0.00 \$0.00 0.00 \$0.00 0.00 \$0.00		\$154.13
Woodleaf Reserve Pha	ase 4				
	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	\$0.00 0.00 \$0.00 2.25 \$92.48 0.00 \$0.00 0.00 \$0.00		\$92.48
City Hall Biofiltration	Device				
	AECOM Bills Engineer Tech Sr. Engineer Tech	\$37.59 \$41.18	\$0.00 0.00 \$0.00 0.00 \$0.00		

Page 83 of 93

	Civil Engineer Chief Engineer-Utilities DPW Director	\$41.10 \$56.32 \$67.34	1.50 0.00 0.00	\$61.65 \$0.00 \$0.00 Total	\$61.65
Baenen_Northview F	AAECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34		\$0.00 \$0.00 \$0.00 \$0.00 464.64 \$50.51 Total	\$515.15
Briohn Builders North	AECOM Bills AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	0.00 0.00 4.00 \$ 0.00 0.00	\$0.00 \$0.00 164.40 \$0.00 \$0.00 Total	\$164.40
Sports Complex Pond	Inspections AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	0.00 0.00 7.00 0.00 0.00	\$0.00 \$0.00 \$0.00 287.70 \$0.00 \$0.00 Total	\$287.70
Rockwood Drive Pond	d Inspection AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	0.00 0.00 0.00 0.00 0.00	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$0.00
Wagner Park Pond In:	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	2.75 \$ 0.00 0.00 0.00 0.00 0.00	\$0.00 103.37 \$0.00 \$0.00 \$0.00 \$0.00 Total	\$103.37
	AECOM Bills Engineer Tech Sr. Engineer Tech Civil Engineer Chief Engineer-Utilities DPW Director	\$37.59 \$41.18 \$41.10 \$56.32 \$67.34	0.00 0.00 0.00 0.00 0.00	\$0.00 \$0.00 \$0.00 \$0.00 \$0.00 \$0.00	\$0.00

Page 84 of 93

	C	
	01	
	1	
	1	
	er	
	P	
	5	
	2	
1	5	
ŀ		
	C	
	0	
•	H	
8	1	
	1	
-	_	
~	0	
1	٦.	

	2020 Budgeted	2020 Expenditure	2021 Budgeted
Catch Basin Cleaning and Maintenance	\$20,636.00	\$29,131.00	\$45,000.00
Storm Inlets and Catch Basins	\$250,000.00	\$192,954.94	\$250,000.00
Street Sweeping	\$20,286.00	\$17,288.79	\$20,286.00
Ditch and Culvert Maintenance	\$225,026.00	\$254,628.72	\$272,796.00
Storm Sewer Maintenance	\$113,287.00	\$54,643.66	\$133,518.00
Yard Maintenance	\$10,000.00	\$0.00	\$10,000.00
Yard Waste Recycling	\$89,991.00	\$91,113.45	\$92,501.10
Totals	\$729,226.00	\$639,760.56	\$824,101.10

Items reported here were typically broken out in the budget. Yard Maintenance used to be found under Permit Compliance. Storm Inlets and Catch Project. Yard Waste Recycling was taken as a fraction of the budgeted and actual expenditures from Refuse Collection and Recycling (10.307% of Basins was found under Storm Water Projects. Ditch and culvert maintenance excludes any improvements associated with the Oak and Peninsula totals).

Storm Water Quality Management

Budget for Reporting Year	\$350,000.00
Expenditures for Reporting Year	\$0.00
Budget for Upcoming year	\$350,000.00

Storm Water Quality Management within the permit is the maintenance of the City's pollution reduction total at the the budgeted costs for a new Storm Water Management Plan found under Projects. This would include a complete time the law was changed to negate the 40% requirement. As there is no budget line item for this, I have included remodel for water quality purposes.

Storm Sewer System Mapping

Budget for Reporting Year	\$5,000.00
Expenditures for Reporting Year	\$6,999.90
Budget for Upcoming year	\$5,000.00

Storm Sewer System Mapping is lumped within Storm Sewer Maintenance budget category. There is not breakout for this Asbuilt And Mapping in the 2020 Budget listing. Carried over the previous year budget amount for reporting purposes.

Item E

Waukesha County Contracted Program Summary Report & 2020-2024 Public Education and Outreach Plan

Description	10	18 soil and water program for earth science class	60 career day at Orchard Lane Elementary				/9 Elimwood Elementary Career Day	Juvided rain barrel and divortor for use of the school	1 provided fairt batter and diverter for use at the school				24 Kettle Moraine School Disrict		32 volunteer appreciation event	64 lunch n learn at Inpro	11 Waukesha Wellness Center Lunch n Learn	spring workshops	spring workshops 154 annual stormwater workshop moved to virtual and was held in May		employee health and wellness fair	Ronald Reagan Elementary career day	grade 2/3 workshop	program at Eagle library	Silver Lake Intermediate School	Silver Lake Intermediate School Silver Lake Intermediate School	Silver Lake Intermediate School	Silver Lake Intermediate School	Silver Lake Intermediate School	Brookfield Elementary	Brookfield Elementary	I composing message to kick on virtual earth week celebration Farth Day Event	Middle school	Muskego HS career day		800. Parkview middle school virtual career day-recorded program available to all students	Sith grade	program at Pewaukee Library	1 May the 4th compositing and healthy soil message	1 Revenge of the 5thturn your soil to the dark sidewith compost!	142 online stormwater workshop - artificial wetlands, green infrastructure and wetlands	135 online stormwater workshop - constructed wetlands, leaf management	20 online rain garden and rain barrel class for Inpro	1 Green cleaners	 rain garden plants for St. Mary's Menomonee Falls how to proportivitize of household supplier and a supplier planting. 	1 how to properly uspose or nazarouus waste write spring cleaning 1 benchmark on Sussex Creek	2 benchmark on Pewaukee River at the junction with the Fox	1 benchmark on Scuppernong river @Hwy Z	1 benchmark on Mukwonago River	1 benchmark for level 2 on Pebble Creek at TT	2 benchmark on Rosenow Creek	I stollitt draitt eudeauori tor world ocean day 3 virtual Green home program through Sussax I ibrary	2 biotic index on Pewaukee River		2 benchmark monitoring on Genesee Creek and Spring Brook
# People		A STATE OF					i	ō	A TONG		State of the state	Succession States			and the second se					COV	COV	COV	COV	COV			COV	COV	COV	COV	COV	COV	COV	COV	COV		COV	COV			1	1	The second se				C Tatt						The second second second		and the set
Location	Oconomowoc	Oconomowoc	New Berlin	Retzer	WCTC	NUCIC	New Derlin	Prairie Hill Waldorf	Waukesha	Waukesha	Waukesha	New Berlin	Retzer	Waukesha	Retzer	Muskego	Waukesha	Reizer	UW-Waukesha	Retzer	Waukesha	New Berlin	Retzer	Concention	Oconomouod	Oconomowoc	Oconomowoc	Oconomowoc	Oconomowoc	Brookfield	Brookfield	Retzer	Retzer	Muskego	Retzer	Mukwonago Retzer	Pewaukee	Pewaukee	State of the state	ototomido	statewide	statewide	Muskego	Manamana Falla	Menomonee rails	Sussex	Waukesha	Eagle	Mukwonago	Waukesha	Oconomowoc	Sussex	Waukesha		Genesee
Date	1-3-20	1-3-20	1-10-20	1-29-29	2-5-20	07-0-7	00 00 0	2-10-20	2-19-20	2-19-20	2-19-20	2-28-20	3-4-20	3-5-20	3-7-20	3-9-20	3-10-20	3-14-20	3-17-20	3-18-20	3-18-20	3-19-20	3-24-20	0-11-50	07-41-4	4-14-20	4-15-20	4-15-20	4-15-20	4-17-20	4 10 20	4-20-20	4-21-20	4-22-20	4-23-20	4-24-20	4-28-20	4-28-20	5-4-20	5-5-20 E E 20		5-7-20	5-12-20		07-81-0	5-26-20	5-29-20	5-28-20	5-29-20	5-30-20	6-8-20 6-8-20	0	122		6-22-20
Year		2020	2020		1000	0202	0202	2020				2020				10.10	2020	0202	2020	and a second				0202	1			ALC: N		Ser la	2020		No.		1	2020			-	2020					0202	No.	Inna	1000			2020		R.C.		2020
Month	Jan	Jan	Jan	Jan	reb	reb Fob	Loh Loh	Feb	Feb	Feb	Feb	Feb	Mar	Mar	Mar	Mar	Mar	Mar	Mar	Mar	Mar	Mar	Mar	Anr	Anr	Apr	Apr	Apr	Apr	Apr	Apr	Apr	Apr	Apr	Apr	Anr	and	Apr	May	May	May	May	May	May	May	May	May	May	May	May	un ui	Jun	Solar Ba		hun
Activity/Event	Presentation	Presentation	Presentation	Presentation	Presentation	Precentation	Dienlave and handoute	Green Schools	Presentation	Presentation	Presentation	Presentation	Presentation	Presentation	Stream Monitoring	Presentation	Presentation	Presentation	Presentation	presentation	Displays and handouts	presentation	presentation	presentation	procentation	presentation	presentation	presentation	presentation	presentation	presentation	presentaton	presentation	presentation	presentation	presentation	presentation	presentation	social media	social media	workshop	workshop	presentation	social media	green scrools social media	Stream Monitoring	Stream Monitoring	Stream Monitoring	Stream Monitoring	Stream Monitoring	stream monitoring social media	presentation	Stream Monitoring		stream monitoring
Program Title	5 soil/water	5 soil/water	5 career	groundwater		5 career	5	0	healthy soils	healthy soils	healthy soils	5 career	healthy soils	home composting		5 green home	F croco homo		8 stormwater wkshop	2 green masters	3	5 career	6 aroon homo		healthy soils	healthy soils	healthy soils	healthy soils	healthy soils	healthy soils	nealthy soils social madia	5 green home	soils	5 career	F corroct	J LAIRE	5 water resources	5 green home	social media	social media	「大山」というないという	3	rain gardens and bar	social media	social media	benchmark	benchmark	benchmark	benchmark	benchmark	benchmark social media	5 green home			benchmark
# Topic #	ю с	5	8	C	0 4	o e.	0 00	5	5	5	5	3	5	5		ლ ს	5 0	2 5	9	1	2	3	5	о <i>и</i> с	2	5	5	5	5	S r	n u	3	5	3	2	n n	3	3	and the second	00	8	8						の語の構造				3	STATE IN		
# Topic #	2 2	N C		0 0	ο α	0		7	3	3	3	2	3	с и	5 0	2 1	0 0	3 1	٢	7	1	7 1		4 00	3	3	3	3	с с	m (0 6	2	с С	2	0 0	2	2	2	S I	0 00	9	9	2 C	V U	0	1 6	6	6	0	5 0	2 (10	6	4	ס מ
Target Audience Topic #	Teachers and Students	Toophom and Students	Teachers and Students	Teachers and Students	Teachers and Students	Teachers and Students	General Public	Teachers and Students	Teachers and Students	Teachers and Students	Teachers and Students	Teachers and Students	Teachers and Students	General Public	General Public	General Public	General Public	General Public	Contractors, Dev. & Consul	Busninesses	General Public	Teachers and Students	General Public	Teachers and Students	Teachers and Students	Teachers and Students	Teachers and Students	Teachers and Students	Teachers and Students	Teachers and Students	General Public	General Public	Teachers and Students	Teachers and Students	General Public Teachers and Students	General Public	Teachers and Students	General Public	General Public	Contractors Dev & Consul	Contractors, Dev. & Consul	Contractors, Dev. & Consul	General Public	General Fublic Teachers and Students	General Public	General Public	General Public	General Public	General Public	General Public	General Public General Public	General Public	General Public	Ganaral Public	

Page 89 of 93

		Current and a second	no afine inality include on		and the second s	1-10-50 VEITEI	
General Public	2	social media	social media	Jul 2020			1 proper disposal of household hazardous waste
General Public		social media	social media	Jul 2020	The second	-25-20	1 adopt a drain promo
General Public	1 - Constanting		news releases/articles	Station of the	-	7-27-20	1 adont a drain prace relasea
General Public	The second se	social media	social media	Total and		06-26-	1 autopt a viraili piese ierease
General Public	and the second second	social media	social media	State and		7 08 00	
General Public		morning hland	news releases/articles	No. of Street, or other		02-02-	
General Public	2	outreach	displays and handouts	E ALLAND		7-20-20	Aucht a drain segment on Morning blend IV show
General Public	2	social media		the stands		7-31-20	
General Public	1		Storm Drain Stenciling	同家道		Manomonea Falls	1 pot waste intessage for tan in an elevator day
General Public	1 Contraction of the local	A STATE OF THE PARTY OF THE PAR	Storm Drain Stenciling	-	20	Brookfield	1 volumeer contacted us and received 00 storm drain markets
General Public	2	social media	social media		20 8-3'20	New York	1 net waste message for work like a don day
General Public	3	social media	social media			20	1 composition message for speak some zucchini on vour pointhom poort dou
General Public	1	social media	social media	100-10	100	20	1 nest on honksAll the May to the Ocean
General Public	3	social media	social media			8-10-20	1 post on boundary in the way to the Ocean
Teachers and Students	6	workshon	teacher workshon	1.22		-8-11-20 Retzer	I post of family care for flaudial lazy day
General Public	6	benchmark	Stream Monitoring	No. No.			4 boothmost flow of Success Comm WorkShop
General Public	A NUTSTAN AND	morning hlend	news releases/articles	NIK CO			I perioritials flow at Sussex Creek
Feachers and Students	32	healthy soils	nresentation			8-10-20 Retroc	I repeat of Auopt a grain segment on Moming Biend 1V Show
General Public	ALL SOLLARS		social media	S Notes	A PARTY		
General Public		adont a drain	Navielattors/articles	1. 4465		02	
General Public	T		inewsiettels/aitudes	No. of the other	00 00 00 00	20	/9 newsletter for adopt a drain participants
General Public	. 12		social media	Sap 2020			I social media post on lawn care
Contractors. Dev. & Consul	7	smart salting	training	The second		20	
Feachers and Students	32	healthy soils	Presentation		and and	20 Mainbacha	20 Striatt salurig rol roads virtual workshop
Teachers and Students	行けにお	healthy soils	presentation			1000	52 victual hoalthy soils program for 2 algorith of Door Office
Feachers and Students	3	healthy soils	presentation				# virtual treditity soils programmers of classes at rose clen
General Public	ALL STORE		social media		100	a-10-20 0-10-20	# Vilual reality soils program for St. Jerome S-fectinical Issues cancelled program 1 social modia about activity
Contractors, Dev. & Consul	7	smart salting	training	C. Land	No.	0-22-20	1 social Illeula about pet waste 10 Cmart Calting Darking for virtual workshar
Teachers and Students	3	healthy soils	Presentation		100	10-1-20 Miskan	
General Public	2		social media				12 programmer and a programmer and a programmer of a progra
Teachers and Students			Presentaiton			10-1-20 Retzer	14 stream life workshop at Retzer for school kids
Feachers and Students	1	and the second second second	Presentation	Oct 2020		10-1-20 Retzer	8 stream life workshop at Retzer for school kids
General Public	日本の		social media				1 World smile day about adopting a storm drain
General Public		outreach	Displays and handouts	Silver I		10-6-20 Oconomowoc	125 National night out event
General Public	3	「日本」「「「「「「「「「」」」」	social media		and the second	10-12-20	1 national farmer day post about testing soils before fertilization
General Public		5	social media				1 national train your brain day crossword puzzle
Leachers and Students	3	healthy soils	Presentation				35 healthy soils for Hadfield Elementary
eachers and Students			Presentation			10-15-20 Retzer	12 stream life workshop at Retzer for school kids
General Public	3	healthy soils	Presentaiton		1000	10-17-20	3 virtual program for science fest
General Public		soils	Presentation			10-15-20	* virtual program for soils and basement wetness for adults as part of science fest
General Public	2		social media			100	
eachers and Students			Presentation				10 stream life workshop at Retzer for school kids
leachers and Students	- 1		Presentation	Sois.		10-27-20 Retzer	7 stream life workshop at Retzer for school kids
General Public		1 111 1	social media	al and			 social media post about using vinegar for green cleaning
Gerreral Public	0 u	nealthy solls	presentation	No. of			4 outdoor classroom on soils
General Dublic	0 0	healthy solls	presentation				3 outdoor classroom on soils
General Public		hoalthy coile	presentation				12 OUTGOOT CLASSFOOTH ON SOILS
Jenetian Fublic		realiny solis	presentation	No. of Street, or Stre			4 outdoor classroom on soils
Concrete Saild Students	0 4	2 Water resources	presentation	Nov 2020		11-5-20 Waukesha	30 virtual program for school district of waukesha
General Public			social media	USUS VON		11-8-20	1 social media post about soil health
General Public	3	healthy soils	presentation	Contraction of the local distribution of the		11-11-20 Retrer	1 autidior classroom on soils
General Public	Contraction of the local distribution of the	healthy soils	procentation	and a	1000		10 Outdoor classicuti un suis
General Public	State of the state		social media				
Teachers and Students	1 3	5	presentation			12-17-20 Sussex	1 social media post addut sait use 18 water testing with biology students
General Public	1 3	5	social media		No.		1 social media post with crossword puzzle
Teachers and Students	ر	5	presentation	(1) (1)	a little	12-22-20 Sussex	14 water tecting with AD students
	ACCESSION OF A DESCRIPTION OF A DESCRIPT		historia in	Number of Street		88	14 Walei lesiling with Ar aunacitie

COV indicates that program was cancelled due to COVID * indicates that there were no participants # technical issues prevented program from happening

Permit Topic Areas I&E Programs 1. Illicit Discharge and Elmination Storm Drain Stenciling 1. Illicit Discharge and Elminate and Mazer Bisposal/Pert Waster Management/Vehicle 1. Illicit Application Displays and Household Elf 1. Social media Social media 1. Yard Waste Social media 1. Yard Waste Social media	ams	Municipal I&E Plan Program Descriptions Continue to promote Storm Drain Stenciling (markers) especially as Stenciling (markers) especially as service learning project X Launch Adopt a Storm Drain Program with press release associated with World Water Day Set goal for # of adopters/year. X	2020	2021	2022 21	. ECUC	2024	Municipal Activities (describe)	Passive or Active P/A
Adopt a Storm Drain Stenciling Adopt a Storm Drain Social media us aste HHW Collections Us Us HHW Collections Us HHW Decorer: Green Edition Programs Programs Displays and Handouts Social media Social media Matershed educational programs						오네 올라 TCOLIN			
Adopt a Storm Drain Adopt a Storm Drain social media us HHW Collections Watershed educational programs HOme Makeover: Green Edition program Green Cleaning and Household Elf programs and and Handouts and watershed educational programs	General Public, Businesses	4	<u>×</u>	×	x	×			Å
social media us social media HHW Collections Watershed educational programs Home Makeover: Green Edition programs Green Cleaning and Household Elf programs Displays and Handouts and Matershed educational programs		media nosts to help with launch of	×	×	×	×			٩
us aste HHW Collections Watershed educational programs Home Makeover: Green Edition programs Green Cleaning and Household Elf programs Displays and Handouts and Matershed educational programs	general public	storm drain program		×	×	×			(_
Matershed educational programs Watershed educational programs Watershed educational programs Home Makeover: Green Edition Program Green Cleaning and Household Elf programs Arid Waste agement/Pesticide and Matershed educational programs Matershed educational programs	General Public	nities to host ts, website to now to	×	×	×	×			. a
Home Makeover: Green Edition program Green Cleaning and Household Elf programs Displays and Handouts Ard Waste agement/Pesticide and Matershed educational programs	Teachers/Students , Beneral public	educational programs that cover pet waste and car washing X		×	×	×			A
Green Cleaning and Household Elf programs Displays and Handouts fard Waste nagement/Pesticide and Watershed educational programs	een Edition General Public	program that covers pet waste, car washing and more X	×	×	×	×			. 4
Displays and Handouts social media Watershed educational programs	iousehold Elf General Public	program that covers toxic cleaners and safer alternatives X	×	×	×	×			
social media Watershed educational programs	General Public	Display that covers pet waste and X	×	×	×	×			۵.
	General Public	timely posts on seasonal topics X	×	×	×	×			ę
	Teachers/Students , al programs general public	educational programs that cover leaf management and fertilizers X	×	×	×	×			٩
Home Makeover: Green Edition program	en Edition General Public	program that covers leaf management and fertilizer use X	<u>×</u>	×	×	×			A
Healthy Soils through Composting program	Composting Teachers/Students	program that covers composting leaves and other yard waste X	×	×	×	×			٩

MS4 Public Education and Outreach Plan for Wa

	Home Composting for Healthy Soils program	General Public	program that covers composting leaves and other yard waste	x	×	×	X			A
	Displays and Handouts	General Public	display with handouts that covers yard waste management and fertilizer use	×	×	×	×			٩
			work with municipalities to		の一般ないのない	のです。	和語のないです。		ちち たちの いちの いちの いちの いちの いちの いちの いちの いちの いちの い	Contraction of the second
			provide processing of yard wastes							
			in partnership with Johnson							
	yard waste collection/processing	municipalities		X X	X	X	X			A
	social media	General public	timely posts on seasonal topics	× ×	×	×	×			۵.
4. Stream and Shoreline			display with handouts that covers			「「「「「「「」」」				
Management	Displays and Handouts	General Public	native plantings for shorelines	X X	X	×	×			d
Pa	Healthy Lakes Conference	Lakeshore property owners	Conference that covers shoreline restoration	×		×				. 4
Residential Infiltration	Rain Barrels/rain gardens workshop	General Public	program covering installation and use of rain gardens and rain barrels	×		×				A
2 of 9	Displays and Handouts	General Public	Display that covers rain gardens and rain barrels as well as native plants	×	×	×	×			<u>م</u>
93					意識と			ないので、「「「「「「」」」	の時代では、「「「「「「」」」」	
	Composting for Healthy Soils workshop	General Public	program that covers using compost to increase infiltration and water holding capacity of soils	X	×		*			A
	social media	General Public	timely posts on seasonal topics	×	×	×	×			
 6. Construction Sites/Post- Construction Stormwater Management 	Annual Stormwater Workshop	Developers. Builders, Contractors, Municipal Staff	workshop that covers a variety of topics regarding constructions sites and BMP management and maintenance	×	×	×	×			Ā
	Homeowners Assocation BMP maintenance workshop	Homeowners Associations	it covers and maintenance for	-	×	×	×			: ح
7. Pollution Prevention	Salt Management for Parking Lots Workshop	Businesses, Municipal staff, school facility staff	workshop that covers salting best management practices for sidewalks and parking lots	×		×				A

	Adopt a Storm Drain	Businesses	Launch Adopt a Storm Drain Program with press release associated with World Water Day Set goal for # of adopters/year.	×	×	×	×	×		<
	business resource webpage	businesses	launch website with resources specific to businesses	×	×	×	×	×		
8. Green Infrastructure/Low Impact Development	Green Infrastructure class	WCTC students	teach session in WCTC class on planning and development/building	×	×	×	×	×		A
	Annual Stormwater Workshop	Developers. Builders, Contractors, Municipal Staff	workshop that covers a variety of topics regarding constructions sites and BMP management and maintenance	×	×	×	×	×		A
B Miscellaneous	Citizen Stream Monitoring	General Public	citizens trained to collect water quality data on local streams	×	×	×	×	×		٨
Je S	Municipal board/council meeting	General Public, elected officials	present annual workplan and report to public	×	×	×	×	×		A
93 of 9	web page	General public	up to date information on pollution prevention and available programs	×	×	×	×	×		۵.
93										

CITY OF PEWAUKEE PUBLIC WORKS COMMITTEE AGENDA ITEM 5.2.

DATE: April 22, 2021

DEPARTMENT: Public Works

PROVIDED BY: Magdelene Wagner

SUBJECT:

Discussion and possible action regarding Kathryn Court/Springdale Estates Flood Mitigation Project alternatives.

BACKGROUND:

Staff received a complaint regarding standing water in the rear yard of a property. Upon review, it was noted this area has had a long standing water ponding issue on the Zignago property. From a review a historical topography and photos, it appears when Kathryn Court subdivision was developed, it was filled and blocked the natural drainage patterns. A 20 foot easement on the subdivision was platted, but does not drain this area.

The City Common Council authorized a study in 2019 which was finalized in 2020. The Study of alternatives was developed to address this long standing issue.

Staff is seeking a recommendation of the recommended alternative for a construction project to address this issue.

FINANCIAL IMPACT:

The 2021 budget included \$500,000.00.

RECOMMENDED MOTION:

Public Works Committee to concur with the report and Staff to recommend Alternative 1 to the Common Council.

ATTACHMENTS:

Description Kathryn Ct Alternatives Report



Technical Memorandum

То	Magdelene Wagner, Director of Public Works, Pewaukee Rich Wirtz, PE, CFM, Chief Engineer-Utilities, Pewaukee Page 1
сс	
Subject	Foxwood – Kathryn Court Drainage Study AECOM Project #: 60339891
From	Steve Parse, PE, CPMSM, Rick Eilertson, PE, Ashley Leisgang, PE
Date	August 21, 2020, Revised September 11, 2020

Introduction

A hydrologic and hydraulic analysis using XP-SWMM, a software program, was conducted by AECOM for the City of Pewaukee. This analysis specifically focused on an area north of Foxwood Lane and along Kathryn Court. The water flows west to east and discharges to the storm sewer system along Springdale Rd.

During storm events, storm water ponds southwest of the Kathryn Court cul-de-sac and north of Foxwood Lane in a localized low spot in an existing ditch (Foxwood ditch). The localized ponding has not impacted the street or neighboring houses, however, local residents have complained of smell and insects as result of standing water. In general, surface water runoff comes from a mix of urban and agricultural areas which drains from the west to the localized low spot southwest of Kathryn Court. The City contracted with AECOM to evaluate alternatives that would improve storm water drainage away from the low spot and ultimately to the Springdale Rd storm sewer system. The location of the ponding, the Foxwood Ditch, and Springdale Rd storm sewer system are found on Figure 1.

The specific goals for this analysis was:

- Document existing drainage issues found within the watershed.
- Evaluate three (3) alternatives that could alleviate the localized flooding and ponded water near Foxwood Lane and Kathryn Court.
- Provide the City with updated storm sewer GIS information based on the site survey.

Background

The objective of this study is to relieve standing water from the ditch located north of Foxwood Lane and southwest of Kathryn Court, in hopes of reducing odor and insects. Historically, the Foxwood ditch conveyed approximately 275 acres of storm water runoff from the upstream portions of the watershed to Springdale Road. The watershed of the Foxwood ditch is shown on Figure 1.



In the late 1980's, the Briarwood Homesites Plat was developed (which includes Kathryn Court and the residential properties around it). During this time, the ditch was relocated from its original location to a public drainage easement in Outlot 1 north of Kathryn Court and South of the Canadian Pacific (CP) Railway via a ditch along the eastern perimeter of the Zignego property. A copy of the Briarwood Homesites Plat showing the public drainage easement is included as Attachment A. The Briarwood Homesites Grading and Erosion Control Plan is included in Attachment B.

GIS contours from 2015, provided by the City, show the bottom of ditch elevation at the start of the Briarwood ditch (~846') is higher than the bottom of ditch elevation of the Foxwood ditch (~844'), creating a low spot at the ponding location. In general, the entire study area is clayey soils within the hydrologic soil groups B/D, C, and D, which allow very little to no infiltration. Visual evidence of standing water in the ponding area even during dry periods further suggests little to no infiltration is occurring in the ditch.

Drainage Conditions

Hydrology

Basins were delineated using 1-foot contour data from 2015 in ArcGIS for the entire study area. Once the basins were delineated, the longest flow paths were drawn, and a spreadsheet was used to determine the Time-of-Concentration (Tc) values for each basin, representing the time that it takes for water to flow from the most remote point in the basin to the outlet node. It was assumed that runoff in the area consists of primarily sheet flow and shallow concentrated flow. Slope flow, flow length, land type, and other factors were considered in the calculations.

In addition, an SCS curve number (CN) was calculated for all basins based on a weighted average using the formula below.

CN_Basin = [(Area_Impervious * CN_Impervious) + (Area_Pervious * CN_Pervious)] / Area_Basin

A CN value of 98 was used for impervious surfaces, and values for pervious surfaces were selected based on the land characteristics of the area, considering that soils are primarily within soil groups C, D, and B/D. Areas were delineated using ArcGIS.

Model Setup

The existing and proposed conveyance system was modeled using Version 2018.2.2 of XP-SWMM software. XP-SWMM is a dynamic model using a link-node representation for ditches/conduits and junctions. The hydrologic calculations for the study area were completed using the SCS runoff method. The amount (volume) of runoff and peak flow (rate) of runoff, generated by each sub-basin area is dependent on the CN and Tc.



The model was run for multiple rainfall events using NOAA Atlas 14, MSE3, 24-hour rainfall distributions. The rainfall depths utilized were:

- 1-year, 24-hour 2.38 in
- 2-year, 24-hour 2.69 in
- 10-year, 24-hour 3.81 in
- 100-year, 24-hour 6.23 in

Existing Conditions

The existing model includes ditches, storm sewers, culverts, and storm water ponds located within the drainage basin. The drainage basin area upstream of the ponding area is approximately 275 acres. As-built drawings and GIS culvert, storm sewer, and topographic contour information were used to build the model. Following an analysis of the collected information, a supplemental site survey was conducted. This was done to verify the as-built and GIS information, and locate additional storm water structures that were not included in the provided information. The survey team also collected data on the ditch cross sections and elevations. The existing GIS shapefiles were then updated with the surveyed and field verified information. This data was then imported from GIS into XP-SWMM software. Ditches were incorporated in XP-SWMM based on the as-builts, GIS contours, and surveyed information. The existing drainage conditions are illustrated on Figure 1.

The Briarwood ditch north of Kathryn Court ends at a weir with a 15-inch culvert near Springdale Road. This weir was designed to control the 10-year peak rate flow from the Briarwood Homesites development (Kathryn Court) and allow overtopping of the weir during larger storm events.

Storm water from the Briarwood ditch is conveyed into a 42-inch storm sewer along the west side of Springdale Road. For the purposes of this study, the 42-inch storm sewer was only analyzed from its inlet north of Kathryn Court to its connection with a 15-inch sewer located south of Kathryn Court and north of Indianwood Court.

Flood Relief Alternative Evaluation

Following the completion of the existing conditions analysis, three potential flood reduction alternatives were evaluated by AECOM and City staff. The existing conditions model was used as a starting point. The following section describes the management alternatives that are modeled.

Proposed - Alternative 1

Alternative 1 involves constructing a 12-inch storm pipe from the ponding area along the Zignego property and through the existing public drainage easement (Outlot 1 of Briarwood Homesites Plat) on the north side of Kathryn Court. The 12-inch storm pipe will outlet into the 42-inch storm sewer system along Springdale Rd. This would drain the area experiencing ponding while minimally affecting flows and/or potential issues downstream.

The 12-inch storm pipe will begin at a structure located at the low point of the ponding area where the Foxwood ditch and Briarwood ditch meet. It is modeled as a catch basin with an invert of 841.50, 2.5 feet below the existing low point in the ditch. The invert is set 2.5 feet below the existing low point of the ponding area so future underdrains can be constructed at the Foxwood ditch as part of a future storm water best management practice (BMP) devise.



The 12" storm pipe will discharge into the 42-inch diameter sewer located on the west side of Springdale Road at the existing manhole northwest of the intersection with Kathryn Court. This will allow for a sufficient slope of 0.32% for the overall proposed pipe.

The layout for Alternative 1 is found in Figure 2.

Proposed - Alternative 2

Alternative 2 involves adding a 12-inch storm pipe from the ponding area, along a small portion of the Zignego property then through an existing 20-foot drainage easement located on the south side of parcels on Kathryn Court. This would drain the area experiencing ponding while minimally affecting flows and/or potential issues downstream.

The 12-inch storm pipe will outlet into a proposed storm sewer on Maplewood Lane. The existing 10and 12-inch diameter storm sewer on Maplewood Lane, is currently undersized resulting in reported localized flooding. Thus, as part of Alternative 2, the Maplewood Lane storm sewers are recommended to be replaced with deeper 18-inch storm pipes to reduce localized flooding and provide the necessary slope to construct the 12-inch storm pipe.

As in Alternative 1, the inlet is modeled as a catch basin with an elevation of 841.50, 2.5 feet below the lowest ditch elevation for future storm water BMP installation while maintaining a slope of 0.39%.

The layout for Alternative 2 is found in Figure 3.

Proposed - Alternative 3

Alternative 3 involves re-grading the ditch along the Zignego property and then through the existing Briarwood ditch (Outlot 1) on the north side of Kathryn Court to obtain positive slope. This would drain the area experiencing ponding.

Alternative 3 will not involve any modifications to the weir structure in the public drainage easement. The layout for Alternative 3 is found in Figure 4.

Model Results

Ponding Area

The model results for the ponding area were analyzed to evaluate the impact of the ponding area in the proposed alternatives when compared to the existing conditions. The water surface elevation (WSE) and the time it takes to drain the ponding area were compared (duration). The ground/overbank elevations represent either the approximate elevation of surrounding structures (i.e. house, garages, sheds) or the surrounding edge of pavement (EOP) of a roadway.

Table 1 summarizes the water surface elevation for the existing conditions and three proposed alternatives. Table 2 summarizes the duration of ponding for each of the alternatives. The location of the XP-SWMM Nodes is found on Figure 1.

XP-	Ground/	Water S	10-year, Surface Ele		SE) (ft)	Wate		r, 24-hour levation (WS	SE) (ft)
SWMM Node ⁽¹⁾	Overbank Elev.	Existing	Alt. 1	Alt. 2	Alt. 3	Existing	Alt. 1	Alt. 2	Alt. 3
Node 1364	855.00 (Structure)	848.86	848.83	848.83	847.29	850.31	850.29	850.29	848.49
Node 1412.1	847.00 (Structure)	845.87	845.86	845.85	846.02	846.86	846.85	846.84	846.83
Node 1413	847.00 (Road)	845.70	845.69	845.64	845.94	846.82	846.82	846.81	846.80
Node 1413.1	843.00 (Road)	843.41	843.45	843.36	843.58	844.36	844.43	844.36	844.34
Node 1414	841.00 (Road)	840.10	840.11	840.07	840.20	840.88	840.90	840.88	840.85
Node 1420	840.00 (Road)	836.05	836.05	836.04	836.06	836.14	836.14	836.14	836.14

Table 1: Water Surface Elevations

(1) For node locations, see Figure 5.

Table 2: Duration of Ponding

		100-year, 24-hou	ur Storm Event	
Scenario	Existing	Alternative 1	Alternative 2	Alternative 3
Duration of Ponding (hours)	>72	22.00	21.75	20.50

In Alternative 1 and 2, the change in peak WSE is negligible relative to the WSE in the existing conditions. However, the ponding area will drain within the recommended 24-hour time frame.

Alternative 2, will also provide improvements to Maplewood Lane. The proposed storm sewer pipes are sized to convey the 10-year 24-hour storm.

Alternative 3, provides the greatest reduction in the peak WSE at the ponding area. The regraded ditch allows the storm water runoff to efficiently drain and move downstream, thus causing an increase in peak WSE through the Briarwood ditch. According to WisDOT FDM 13-20-1, ditches are recommended to have a minimum slope of 0.5% with an absolute minimum slope of 0.3% to allow for proper drainage. The slope for Alternative 3 is limited to 0.09%. Due to the low slope and increased peak WSE downstream, this alternative is not recommended.



Drainage Basin Upstream of Ponding Area

This model can be utilized to analysis potential concerns upstream of the Foxwood ditch. The City typically designs new storm sewer systems to convey a minimum of the 10-year – 24-hour storm event. There are many locations throughout this basin where the existing storm sewer does not meet this criteria.

As the existing condition results were analyzed, there were three locations that appeared to have greater recurrence in surface ponding. The following locations experience flooding for storm events greater than the 1-year, 24-hour storm:

- A. Duplainville Road below the CP Railway
- B. Storm water easement south of Kathryn Court and north of Indianwood Court between Maplewood Lane and Springdale Road
- C. Foxwood Lane north of the intersection with Foxwood Court

Opinion of Probable Cost

Opinions of Probable Cost (OPCs) for the three alternatives are summarized in Table 3. Details spreadsheets for each alternative can be found in Attachment C.

Alternative	Cost
1	\$274,000
2	\$1,004,000
3	\$349,000

Table 3: Opinion of Probable Cost Summary



Recommendations

Considering cost, constructability, and achieving the goal of eliminating the standing water in the ponding area without adversely affecting the drainage conditions downstream, Alternative 1 is the recommended option. Further, Alternative 1 provides opportunity for potential conversion of the Foxwood ditch into a biofilter or similar best management practice that could help improve water quality of the downstream waters which may prove useful in meeting future Total Maximum Daily Load (TMDL) requirements for the watershed.

Attachments

- A Briarwood Homesites Plat
- B Briarwood Homesites Grading & Erosion Control Plan
- C Opinions of Probable Cost Spreadsheets

Figures


- 1 Drainage Basin Study Area
- 2 Alternative 1
- 3 Alternative 2
- 4 Alternative 3
- 5 XP SWMM Model Node Locations




Attachments



Attachment A










Attachment B



Page 13 of 23



Attachment C

	CLIENT:	City of Pewaukee				
AECOM	PROJECT:	Stormwater Management Plan Review Assistance				
	CONTRACT NO:): Foxwood-Kathryn Court Drainage Study Tasks				
1555 Rivercenter	AECOM PROJECT NO.:	60339891				
Dr., Suite 214	SUBMITTAL:	Opinion of Probable Construc	tion Cost			
Milwaukee, Wisconsin 53212	DATE CREATED/MODIFIED:	08/12/2020	BY:	SDP		
	DATE CHECKED:	08/12/2020	BY:	RE		
Opinion of Probable Construction Cost						
Line Item Item Code	Item Description	Unit of Measure Quantity	/ Unit Price	Total Cost		

Line Item	Item Code	Item Description	Unit of Measure	Quantity	Unit Price	Total Cost
1	619.1000	Mobilization, Bonds, and Insurance (~7%)	LS	1	\$14,000	\$14,000
2	SP	Clearing & Grubbing	LS	1	\$15,000.00	\$15,000
3	628.1504	Silt Fence	LF	2,036	\$3.00	\$6,108
4	628.7504	Ditch Checks	LF	90	\$15.00	\$1,350
5	628.7560	Tracking Pad	EACH	1	\$3,500.00	\$3,500
	SP	6" Topsoil Restoration, w/ Class 1, Urban, Type B Erosion	SY			
6		Mat		4,500	\$5.00	\$22,500
7	630.0140	Turfgrass Seed Mix	SY	4,500	\$2.00	\$9,000
7	SP	Storm Sewer Pipe HDPE 12-Inch	LF	1,990	\$60.00	\$119,400
8	SP	Drop Inlet Structure w/ Grate	EACH	1	\$2,000.00	\$2,000
9	611.2004	Manholes 4-FT Diameter w/ Casting	EA	6	\$2,000.00	\$12,000
10	SP	Construction Staking Storm Sewer	LS	1	\$1,500.00	\$1,500
11	416.1720	Concrete Flume Removal and Replacement	SY	50	\$80.00	\$4,000
12	SP	Core into Existing Storm Manhole	EA	1	\$750.00	\$750

Total Opinion of Probable Construction Cost \$198,000

Surveying & Design Engineering (~10%) \$20,000

Construction Administration/Observation (~10%) \$20,000

Contingency (~15%) \$36,000

Total Opinion of Probable Surveying, Engineering Design, Construction, and Administration/Inspection Cost Estimate \$274,000

		CLIENT:	City of Pewaukee			
AECOM PROJECT: S		Stormwater Management Plan Review Assistance				
		CONTRACT NO:	Foxwood-Kathryn C	ourt Drainag	e Study Tasks	
1555 Rive	ercenter	AECOM PROJECT NO.:			-	
Dr., Suite		SUBMITTAL:				
Milwauke	e,	DATE CREATED/MODIFIED:	08/06/2020		BY:	SDP
Wisconsir	n 53212					
		DATE CHECKED:	CKED: 08/13/2020 BY:		RE	
Line Item	Item Code	Item Description	Unit of Measure	Quantity	Unit Price	Total Cost
1	619.1000	Mobilization, Bonds, and Insurance (~7%)	LS	1	\$51,000	\$51,000
2	SP	Clearing & Grubbing	LS	1	\$5,000.00	\$5,000
3	628.1504	Silt Fence	LF	200	\$3.00	\$600
4	628.7504	Ditch Checks	LF	20	\$15.00	\$300
5	628.7560	Tracking Pad	EACH	2	\$3,500.00	\$7,000
	SP	6" Topsoil Restoration, w/ Class 1, Urban, Type B Erosion	SY			
6		Mat		500	\$5.00	\$2,500
7	630.0140	Turfgrass Seed Mix	SY	500	\$2.00	\$1,000
8	SP	Storm Sewer Pipe HDPE 12-Inch via Trenchless Installation		1,115	\$525.00	\$585,375
9	SP	Storm Sewer Pipe RCP 18-Inch	LF	40	\$80.00	\$3,200
10	SP	Storm Sewer Pipe HDPE 18-Inch via Trenchless Installation	LF	185	\$575.00	\$106,375
11	SP	Drop Inlet Structure w/ Grate	EACH	1	\$2,000.00	\$2,000
12	SP	Remove and Replace Inlets, 2' x 3', w/ Casting and Grate	EA	3	\$2,000.00	\$6,000
13	SP	Construction Staking Storm Sewer	LS	1	\$1,500.00	\$1,500
14	SP	Curb and Gutter Removal and Replacement	LF	40	\$25.00	\$1,000
45	00	Asphalt Roadway and CABC Removal and Replacement	SY	75	¢50.00	¢0.750
15	SP		= .	75	\$50.00	\$3,750
16	SP	Core into Existing Field Inlet	EA Total Opinion of Pr	1	\$750.00	\$750

Total Opinion of Probable Construction Cost \$727,000

Surveying & Design Engineering (~10%) \$73,000

Construction Administration/Observation (~10%) \$73,000

Contingency (~15%) \$131,000

Total Opinion of Probable Surveying, Engineering Design, Construction, and Administration/Inspection Cost Estimate \$1,004,000

			City of Pewaukee			
AECOM		PROJECT:	Stormwater Management Plan Review Assistance			
		CONTRACT NO:	D: Foxwood-Kathryn Court Drainage Study Tasks			
1555 Rive	ercenter	AECOM PROJECT NO .:	60339891			
Dr., Suite	214	SUBMITTAL:				
Milwauke	,	DATE CREATED/MODIFIED:	08/06/2020		BY:	SDP
Wisconsir	1 53212	DATE CHECKED:	08/13/2020		BY:	RE
Line Item	Item Code	Item Description	Unit of Measure	Quantity	Unit Price	Total Cost
1	619.1000	Mobilization, Bonds, and Insurance (~7%)	LS	1	\$18,000	\$18,000
2	SP	Clearing & Grubbing	LS	1	\$30,000.00	\$30,000
3	628.1504	Silt Fence	LF	200	\$3.00	\$600
4	628.7504	Ditch Checks	LF	360	\$15.00	\$5,400
5	628.7560	Tracking Pad	EACH	1	\$3,500.00	\$3,500
6	205.0100	Excavation Common	CY	4,400	\$22.00	\$96,800
7	SP	6" Topsoil Restoration, w/ Class 1, Urban, Type B Erosion Mat	SY	7,800	\$5.00	\$39,000
8	630.0140	Turfgrass Seed Mix	SY	7,800	\$2.00	\$15,600
9	SP	Construction Staking	LS	1	\$3,500.00	\$3,500
10	416.1720	Concrete Flume Removal and Replacement	SY	700	\$80.00	\$56,000
			Total Opinion of Pr	obable Cons	struction Cost	\$251,000

Surveying & Design Engineering (~10%) \$26,000


Construction Administration/Observation (~10%) \$26,000

Contingency (~15%) \$46,000


Total Opinion of Probable Surveying, Engineering Design, Construction, and Administration/Inspection Cost Estimate \$349,000




Figures




C:\Users\steve.parse\Desktop\Pewaukee\Memo\FIGURES\Figure 1_v2_11x17-Landscape.m




C:\Users\steve.parse\Desktop\Pewaukee\Memo\FIGURES\Figure 2_v2_11x17-Landscape.mxd





C:\Users\steve.parse\Desktop\Pewaukee\Memo\FIGURES\Figure 4_v2_11x17-Landscape.mxd



CITY OF PEWAUKEE PUBLIC WORKS COMMITTEE AGENDA ITEM 6.1.

DATE: April 22, 2021

DEPARTMENT: PW - Water/Sewer

PROVIDED BY: Magdelene Wagner/Jane Mueller

SUBJECT:

Discussion and possible action regarding the Well 5 HMO Treatment Facility & Building update.

BACKGROUND:

Well #5 is located on Northmound Dr. in the Bluemound Industrial Park in the northwest corner of Bluemound Rd and Springdale Rd. The well drilled in 1992 drilled to a depth of 1000 ft. At the time, we were told that it was quite an unusual well in that caverns containing pyrite were seen in the well videos. Since the well siting, we have come to learn that this site is likely in close proximity of the Waukesha Fault line.

At the end of 2010, the Utility started to experience Gross Alpha exceedances from this well, eventually causing us to be in non-compliance with Gross Alpha and enforcement of a DNR Consent Order in August 2014. This required the Utility to investigate several treatment systems for removal of Gross Alpha (radiologicals) in the well. Pilot testing of the well took place in 2015 and a treatment system was identified and preliminary design of the treatment system took place.

As a result of the Gross Alpha exceedance, the Utility reduced the use of this well. The site continued to be used periodically throughout each month and was utilized more frequently during high demand periods or when we had other well pumps out of service. The well and reservoir was also available to meet fire protection demand for the area. During this period of reduced use, the Utility found that the levels of Gross Alpha diminished. In 2016, the site became compliant with Gross Alpha without adding treatment and the Consent Order was closed in August 2016.

In 2018 - 2019 we began to experiencing the rise in the levels of Radium 226/228 eventually leading to non-compliance and Consent Order for Radium in September 2020. The draft treatment plant plans were resurrected and updated. Plan approvals were received from the DNR and later the Public Service Commission.

In preparation of the construction of the treatment plant, staff took the pump station off line. Staff emptied and cleaned the reservoir for our 5 year inspection. Unfortunately, they discovered a roof leak in the reservoir. Also the piping internal to the reservoir showed coating failure.

The Utility also planned to conduct well and pump maintenance at the site to make sure the pump and motor work was completed prior to construction. Consultant's review of old well video identified that the well had partially collapsed or bridged. A contractor was hire to pull the pump and attempt to remove the bridge.

The replacement of the reservoir roof membrane and the replacement well pump and motor were included in the contracts for the HMO treatment plant construction.

The contractor videotaped the well after pulling the pump. The video showed the bore hole has several areas of unconsolidated formation. Typical (good) well formations will have smooth bore holes with cracks or seams that will be seen along the walls. There are areas of this well that look like loose cobblestones. The contracts attempt to remove the collapse were futile as the equipment kept getting stuck. Additionally, there is major concern about the water quality in

this well. There is significant microbiological activity.

To date.

The condition of the well formation if very concerning to Staff. We are concerned that due to the unconsolidated nature of this well that the well could continue to deteriorate over time. Particularly when quarrying starts to the west of the pump station. The construction of the treatment system and garage are estimated at \$3.4 million. That is a huge investment that may not be reliable in the future. The Utility is holding the bids for the construction of the treatment plant at this time. We have asked our consultants to prepare a formal request to the DNR asking for a time extension for our Consent Order that requires compliance by May 31, 2023.

Staff recommends requesting an extension of the consent order by one year to May 31, 2024. This will allow staff time to work with either identifying ways to fortify the current well formation that would give more assurance that the well won't continue to collapse or identify an alternative supply to this well; whether that be additional water main loops or well site.

FINANCIAL IMPACT:

RECOMMENDED MOTION:

CITY OF PEWAUKEE PUBLIC WORKS COMMITTEE AGENDA ITEM 8.1.

DATE: April 22, 2021

DEPARTMENT: PW - Engineering

PROVIDED BY:

SUBJECT:

Discussion and possible action regarding a pedestrian crossing across Green Road from Littlefield Court to private Five Fields Park.

BACKGROUND:

Staff was approached by several Five Fields residents and the Homeowners Association President regarding replacing a crosswalk across Green Road from Littlefield to the private Five Fields Park. During the reconstruction of Green Road in 2012, Staff was not aware of this crossing, but in review of historical aerials, a pedestrian crossing was present. This crossing was not maintained which is why it was not installed as part of the reconstruction of Green Road.

The HOA is asking for a new crossing to be installed to the private Five Fields Park. The Bike & Pedestrian Committee concurred with installing a pedestrian crossing at this location at the March 24, 2021 meeting. The crossing will require curb cuts, handicamp ramps, etc to be in compliance with ADA requirements.

FINANCIAL IMPACT:

A cost estimate has not been created for this work. It would be included in the 2022 budget if authorized.

RECOMMENDED MOTION:

ATTACHMENTS:

Description 2005 Aerial 2020 Aerial




Waukesha County GIS Map





LAND INFORMATION SYSTEMS DIVISION

Waukesha County GIS Map



CITY OF PEWAUKEE PUBLIC WORKS COMMITTEE AGENDA ITEM 8.2.

DATE: April 22, 2021

DEPARTMENT: Public Works

PROVIDED BY: Magdelene Wagner

SUBJECT:

Discussion and possible action to establish future meeting date and times.

BACKGROUND:

Staff is looking to hold regular Public Works Committee meeting at a frequency of once per month. We would like to find a regular time that will work for all committee members. Please bring your schedule to review a time and date for future meetings.

FINANCIAL IMPACT:

RECOMMENDED MOTION:

CITY OF PEWAUKEE PUBLIC WORKS COMMITTEE AGENDA ITEM 8.3.

DATE: April 22, 2021

DEPARTMENT: PW - Engineering

PROVIDED BY: Magdelene Wagner

SUBJECT:

Discussion and possible action regarding Duplainville Road Reconstruction and Trail construction including Lindsay Road Trail construction.

BACKGROUND:

Duplainville Road is in poor condition and is in the City's plan to complete a reconstruction in 2022. As such, Staff has begun the design of the roadway.

Given the local arterial nature of this roadway and the trucking that occurs along the corridor, Staff hired a consultant to review a few alternatives for the road section and composition. See the attached Alternative Analysis.

The first alternative included asphalt as the surface for the entire length of the roadway for an estimated cost of \$5,688.500. The second alternative included concrete as the surface for the entire length of the roadway for an estimated cost of \$7,188,500. The third alternative included asphalt north of Capital Drive and concrete south of Capital Drive for an estimated cost of \$6,188,500. The third alternative was reviewed as the truck turning movements caused by the Quad Graphics operations take place south of Capital Drive and have a large impact on the roadway while north of Capital Drive, it is mainly a through trucking route which has less impact on the roadway.

In general, a concrete roadway will hold up better when there are large amounts of truck turning movements. In addition, concrete generally has a longer life than asphalt pavements. However, we have not completed a full life cycle cost to compare these types of payments at this time.

Staff would like to recommend pursuing the concrete roadway and complete the life cycle cost analysis to confirm this is the best decision long term for the City.

As part of the road reconstruction, the City has authorized installing a trail system along Duplainville Road in conformance with the Bike & Pedestrian Plan. The Bike and Pedestrian Committee recommended an off trail system preferably on the west side of Duplainville Road. However, topography and existing impediments indicate the east side is a more economical location. Therefore, a 10' wide bike/pedestrian path is planned for the east side. The estimated cost for this trail is \$361,500 when completed as part of the road project.

Just recently, the Common Council authorized the design of the trail along Lindsay Road from Duplainville Road to the Pewaukee Sports Complex to be completed as part of this project. The Bike and Pedestrian Committee also recommended an off road system on the north side of Lindsay Road. A cost estimate has not yet been prepared for this portion of a trail.

The above costs do not include any land acquisition costs which will likely be required from 10 properties to accommodate the bike/pedestrian path. This is being further analyzed to determine the final impacts, but the road

section needs to be decided first.

FINANCIAL IMPACT:

RECOMMENDED MOTION:

Public Works Committee recommend pursuing a concrete roadway for the entire length (alternative 2) with a life cycle cost analysis being completed.

ATTACHMENTS:

Description Duplainville Road and Trail Alternative Analysis



November 24, 2020

Ms. Magdelene Wager City of Pewaukee W240 N3065 Pewaukee Road Pewaukee, WI 53072

Re: Duplainville Road Reconstruction Alternative Analysis City of Pewaukee, Wisconsin (City)

Dear Ms. Wager,

The City has hired Strand Associates, Inc.[®] to complete an alternative analysis for the reconstruction of Duplainville Road from just south of Green Road to Weyer Road. A total of three alternatives were evaluated for the Duplainville Road reconstruction analysis. The proposed typical section for all alternatives is an undivided two-lane roadway with 12-foot lanes, 5-foot paved shoulders, 3-foot aggregate shoulders, 16-foot-wide ditches, and an 8-foot-wide paved path outside of the ditch along the east side of the roadway. The proposed typical section includes 30-inch curb and gutter near the intersection with Green Road and the underpass at Capitol Drive. Additional curb and gutter may be required as determined necessary in the design phase. Right-of-way (ROW) impacts are expected because of the path throughout the project area; those costs have not been quantified. Approximately one acre of fee ROW will be required with the addition of the path, and temporary limited easements (TLE) will be required for grading. Enclosed is a typical section and project overview map demonstrating the conceptual layout.

An opinion of probable construction costs (OPCC) was prepared for the following alternatives:

1. Alternative 1–Asphalt Pavement Throughout the Entire Corridor

The asphalt pavement structure includes 2-inches of 4 LT 58-28 S over 4-inches 3 LT 58-28 S over 5 inches of 3/4-inch base aggregate dense (BAD) over 8 inches of 1 1/4-inch BAD.

2. Alternative 2–Concrete Pavement Throughout the Entire Corridor

The concrete pavement structure includes 7 inches of concrete pavement over 3 inches of 3/4-inch BAD over 5 inches of 1 1/4-inch BAD.

3. Alternative 3–Concrete Pavement from the South Project Limits to Capitol Drive, and Asphalt Pavement From Capitol Drive to the North Limit

The pavement structures listed for Alternatives 1 and 2 were used for Alternative 3.

Pavement structures used for this alternative analysis were based on the findings from the Duplainville Road Bridge Replacement project (Wisconsin Department of Transportation ID: 2370-04-70) pavement design, as well as the City Technical Standards. Further analysis to determine final pavement structure will be completed during final engineering and will be based on the geotechnical report and pavement structure design. This additional analysis will gather soil borings throughout the project corridor and account for the different traffic and truck volumes that are experienced within the

 $ALP:nb2\S:\MIL\4600-4699\4621\005\Designs-Studies-Reports\OPCC\Summary\ Letter.docx$

Texas | Wisconsin

Ms. Magdelene Wager City of Pewaukee Page 2 November 24, 2020

project limits. Additional geotechnical analysis will also provide insight to an anticipated amount of excavation below subgrade, which can have a significant impact on overall project cots. Final design standards may influence the OPCC. A preliminary OPCC for each alternative can be found in Table 1.

A more detailed OPCC for each alternative is enclosed. A life-cycle cost analysis was not completed as a part of this evaluation. The trail OPCC should only be considered when included with the roadway reconstruction. Should the City construct the path independent of the roadway, the OPCC will increase. The bid items for the trail OPCC include excavation common, 1 1/4-inch BAD, and asphaltic surface needed for the footprint of the 8-foot-wide trail.

Should you have any questions or like to discuss further, please call me at 414-271-0771.

Sincerely,

STRAND ASSOCIATES, INC.®

ev L. Pridemore, P.E.

Enclosures

 $ALP:nb2\S:\MIL\4600--4699\4621\005\Designs-Studies-Reports\OPCC\Summary\ Letter.docx$

Duplainville Road Alternative 1: Asphalt from Green Road to Weyer Road Preliminary Opinion of Probable Construction Cost November 23, 2020

	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE		TOTAL
	EARTHWORK					
	Excavation Common	CY	68,100	\$15.00	\$	1,021,500
1			Earthwork	Subtotal Cost	\$	1,021,500
	PAVING ITEMS					
	Base Aggregate Dense 1 1/4-Inch	TON	29,700	\$20.00	\$	594,000
	Base Aggregate Dense 3/4-Inch	TON	22,800	\$17.00	\$	387,600
	Concrete Pavement 7-Inch	SY		\$55.00	\$	-
	Concrete Driveway 6-Inch	SY	25	\$53.00	\$	1,300
	HMA Pavement 3 LT 58-28 S	TON	11,900	\$70.00	\$	833,000
	HMA Pavement 4 LT 58-28 S	TON	5,700	\$80.00	\$	456,000
	Concrete Curb & Gutter 30-Inch Type A	LF		\$30.00	\$	-
	Concrete Curb & Gutter 30-Inch Type D	LF	800	\$30.00	\$	24,000
2			Paving Items	Subtotal Cost	\$	2,295,900
	TRAIL ITEMS					
	Excavation Common	CY	2,700	\$15.00	\$	40,500
	Base Aggregate Dense 1 1/4-Inch	TON	4,500	\$20.00	\$	90,000
	Asphaltic Surface (Bike Path)	TON	2,200	\$105.00	\$	231,000
3			Trail Items	Subtotal Cost	\$	361,500
4	Major Roadway Items Subtotal Cost (Lines 1 - 3)					3,679,000
5	ALLOWANCE FOR UNMEASURED ITEMS IN 1-2 ABOVE	LS	25 % of Line 4	N/A	\$	920,000
6	Major F	Roadway	Items Subtotal Co	st (Lines 4 - 5)	\$	4,599,000
	OTHER ITEMS					
7	EROSION CONTROL/FINISHING	LS	5 % of Line 6	N/A	\$	230,000
8	DRAINAGE/STORM SEWER/DITCH GRADING	LS	7 % of Line 6	N/A	\$	321,900
9	SIGNING	LS	2 % of Line 6	N/A	\$	92,000
10	MISCELLANEOUS ITEMS	LS	15 % of Line 6	N/A	\$	689,900
11	PAVEMENT MARKING	LS	2 % of Line 6	N/A	\$	92,000
12		Other	tems Subtotal Cos	st (Lines 7 - 11)	\$	1,426,000
	Total Cost (Lines 6 and 12)					6,025,000
OPINIC	ON OF PROBABLE CONSTRUCTION COST				\$	6,050,000

Assumptions/Notes

- 1. Quantities are based on preliminary layout and 2020 prices.
- 2. Unit costs were taken from BidX using WisDOT projects in and around Waukesha county, as well as WisDOT average bid item prices.
- 3. Costs for items not measureable at the pre-30 percent design stage were determined by reviewing similar projects and what percentage these unmeasurable items typically comprised of the total removals, earthwork and paving items.
- 4. A pavement structure of 7-Inches of Concrete Pavement over 3-Inches B.A.D. 3/4-inch over 5-Inches B.A.D. 1 1/4-inch was used base on WisPave analysis. A pavement structure of 6-Inches HMA pavement over 5-Inches B.A.D. 3/4-inch over 8-Inches B.A.D. 1 1/4-inch was used
- 5. Anticipated FEE and TLE costs not included.
- 6. Earthwork was approximated using the pavement structure depth multiplied by the length of the project.

Duplainville Road Alternative 2: Concrete from Green Road to Weyer Road Preliminary Opinion of Probable Construction Cost November 23, 2020

	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE		TOTAL
	EARTHWORK					
	Excavation Common	CY	56,200	\$15.00	\$	843,000
1			Earthwork	Subtotal Cost	\$	843,000
	PAVING ITEMS					
	Base Aggregate Dense 1 1/4-Inch	TON	18,700	\$20.00	\$	374,000
	Base Aggregate Dense 3/4-Inch	TON	16,300	\$17.00	\$	277,100
	Concrete Pavement 7-Inch	SY	48,800	\$55.00	\$	2,684,000
	Concrete Driveway 6-Inch	SY	25	\$53.00	\$	1,300
	HMA Pavement 3 LT 58-28 S (for driveways)	TON	516	\$70.00	\$	36,100
	HMA Pavement 4 LT 58-28 S	TON		\$80.00	\$	-
	Concrete Curb & Gutter 30-Inch Type A	LF	800	\$30.00	\$	24,000
	Concrete Curb & Gutter 30-Inch Type D	LF		\$30.00	\$	-
2			Paving Items	Subtotal Cost	\$	3,396,500
	TRAIL ITEMS				•	
	Excavation Common	CY	2,700	\$15.00	\$	40,500
	Base Aggregate Dense 1 1/4-Inch	TON	4,500	\$20.00	\$	90,000
	Asphaltic Surface (Bike Path)	TON	2,200	\$105.00	\$	231,000
3		-	Trail Items	Subtotal Cost	\$	361,500
4	Major	Roadway	Items Subtotal Co	st (Lines 1 - 3)	\$	4,601,000
5	ALLOWANCE FOR UNMEASURED ITEMS IN 1-2 ABOVE	LS	25 % of Line 4	N/A	\$	1,150,000
6	Major F	Roadway	Items Subtotal Cos	st (Lines 4 - 5)	\$	5,751,000
	OTHER ITEMS					
7	EROSION CONTROL/FINISHING	LS	5 % of Line 5	N/A	\$	287,600
8	DRAINAGE/STORM SEWER/GRADING	LS	7 % of Line 5	N/A	\$	402,600
9	SIGNING	LS	2 % of Line 5	N/A	\$	115,000
10	MISCELLANEOUS ITEMS	LS	15 % of Line 5	N/A	\$	862,700
11	PAVEMENT MARKING	LS	2 % of Line 5	N/A	\$	115,000
12	Other Items Subtotal Cost (Lines 7 - 11)					1,783,000
	Total Cost (Lines 6 and 12)					7,534,000
OPINIC	ON OF PROBABLE CONSTRUCTION COST				\$	7,550,000

Assumptions/Notes

- 1. Quantities are based on preliminary layout and 2020 prices.
- 2. Unit costs were taken from BidX using WisDOT projects in and around Waukesha county, as well as WisDOT average bid item prices.
- 3. Costs for items not measureable at the pre-30 percent design stage were determined by reviewing similar projects and what percentage these unmeasurable items typically comprised of the total removals, earthwork and paving items.
- 4. A pavement structure of 7-Inches of Concrete Pavement over 3-Inches B.A.D. 3/4-inch over 5-Inches B.A.D. 1 1/4-inch was used base on WisPave analysis. A pavement structure of 6-Inches HMA pavement over 5-Inches B.A.D. 3/4-inch over 8-Inches B.A.D. 1 1/4-inch was used
- 5. Anticipated FEE and TLE costs not included.
- 6. Earthwork was approximated using the pavement structure depth multiplied by the length of the project.

Duplainville Road


Alternative 3: Concrete from Green Road to Capitol Drive and Asphalt from Capitol Drive to Weyer Road Preliminary Opinion of Probable Construction Cost

	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE		TOTAL
	EARTHWORK					
	Excavation Common	CY	65,000	\$15.00	\$	975,000
1			Earthwork	Subtotal Cost	\$	975,000
	PAVING ITEMS					
	Base Aggregate Dense 1 1/4-Inch	TON	26,500	\$20.00	\$	530,000
	Base Aggregate Dense 3/4-Inch	TON	22,000	\$17.00	\$	374,000
	Concrete Pavement 7-Inch	SY	14,900	\$55.00	\$	819,500
	Concrete Driveway 6-Inch	SY	25	\$53.00	\$	1,300
	HMA Pavement 3 LT 58-28 S	TON	8,500	\$70.00	\$	595,000
	HMA Pavement 4 LT 58-28 S	TON	4,000	\$80.00	\$	320,000
	Concrete Curb & Gutter 30-Inch Type A	LF	700	\$30.00	\$	21,000
	Concrete Curb & Gutter 30-Inch Type D	LF	150	\$30.00	\$	4,500
2			Paving Items	Subtotal Cost	\$	2,665,300
	TRAIL ITEMS			•		
	Excavation Common	CY	2,700	\$15.00	\$	40,500
	Base Aggregate Dense 1 1/4-Inch	TON	4,500	\$20.00	\$	90,000
	Asphaltic Surface (Bike Path)	TON	2,200	\$105.00	\$	231,000
3				Subtotal Cost	\$	361,500
4	Major	Roadway	v Items Subtotal Co	ost (Lines 1 - 3)	\$	4,002,000
5	ALLOWANCE FOR UNMEASURED ITEMS IN 1-2 ABOVE	LS	25 % of Line 3	N/A	\$	1,001,000
6	Major F	Roadway	Items Subtotal Co	st (Lines 4 - 5)	\$	5,003,000
	OTHER ITEMS	-			1	
7	EROSION CONTROL/FINISHING	LS	5 % of Line 5	N/A	\$	250,200
8	DRAINAGE/STORM SEWER/GRADING	LS	7 % of Line 5	N/A	\$	350,200
9	SIGNING	LS	2 % of Line 5	N/A	\$	100,100
10	MISCELLANEOUS ITEMS	LS	15 % of Line 5	N/A	\$	750,500
11	PAVEMENT MARKING	LS	2 % of Line 5	N/A	\$	100,100
12		Other	Items Subtotal Cos	st (Lines 7 - 11) Lines 6 and 12)	\$	1,551,000
		\$	6,554,000			
OPINION OF PROBABLE CONSTRUCTION COST					\$	6,550,000

November 23, 2020

Assumptions/Notes

- 1. Quantities are based on preliminary layout and 2020 prices.
- 2. Unit costs were taken from BidX using WisDOT projects in and around Waukesha county, as well as WisDOT average bid item prices.
- 3. Costs for items not measureable at the pre-30 percent design stage were determined by reviewing similar projects and what percentage these unmeasurable items typically comprised of the total removals, earthwork and paving items.
- 4. A pavement structure of 7-Inches of Concrete Pavement over 3-Inches B.A.D. 3/4-inch over 5-Inches B.A.D. 1 1/4-inch was used base on WisPave analysis. A pavement structure of 6-Inches HMA pavement over 5-Inches B.A.D. 3/4-inch over 8-Inches B.A.D. 1 1/4-inch was used
- 5. Anticipated FEE and TLE costs not included.
- 6. Earthwork was approximated using the pavement structure depth multiplied by the length of the project.



FILE NAME : \$\$....designfile....\$\$

COUNTY:WAUKESHA	TYPICAL SECTIONS

PLOT DATE : \$\$...plottingdate...\$\$ PLOT BY : \$\$...plotuser...\$\$ PLOT NAME :

2



CITY OF PEWAUKEE PUBLIC WORKS COMMITTEE AGENDA ITEM 8.4.

DATE: April 22, 2021

DEPARTMENT: Public Works

PROVIDED BY: Magdelene Wagner

SUBJECT:

Discussion regarding Novus Training for Committee Members.

BACKGROUND:

The City of Pewaukee typically distributes the agenda packets and information through Novus Agenda. In order to complete this, we need to schedule a time for some basic training on how to use Novus Agenda. Staff can have this training ahead of the next meeting or at some other time before the next meeting at your preference.

FINANCIAL IMPACT:

RECOMMENDED MOTION: